Stormwater Coalition of Albany County

Oversight of the NYSDEC Construction Activity Permit

SPDES General Permit No. GP-0-15-002

A Guidance Document for MS4s and Other Stormwater Practitoners

SWPPP Oversight Forms for MS4s SWPPP Content Check Lists

(Release Date: March 23, 2016)



Stormwater Coalition of Albany County 175 Green Street, Room B042, Albany, NY 12202 518-447-5645 518-447-5622 (fax) www.stormwateralbanycounty.org <u>swcoalition@albanycounty.com</u>

;

Members

Traditional Land Use Control MS4s (SPDES MS4 Permit No.): City of Albany (NYR20A464); Town of Bethlehem (NYR20A208); City of Cohoes (NYR20A243); Town of Colonie (NYR20A190); Village of Colonie (NYR20A076); Village of Green Island (NYR20A377); Town of Guilderland (NYR20A211); Village of Menands (NYR20A144); Town of New Scotland (NYR20A463); City of Watervliet (NYR20A087). **Traditional Non Land Use Control MS4:** Albany County (NYR20A359). **Non-Traditional MS4:** University at Albany-SUNY (NYR20A234).

ACKNOWLEDGMENTS

This Guidance Document was developed by the Forms Committee of the Stormwater Coalition of Albany County. The collective experience of Committee participants includes SWPPP design; SWPPP review; site inspections during construction; developing and implementing maintenance agreements; and inspection of post construction stormwater practices. Together the Committee represents a wide variety of MS4/municipal types, with two of the MS4 municipalities also responsible for a Combined Sewer Overflow (CSO) SPDES Permit and the related Albany Pool Long Term Control Plan (*).

The content of this document reflects the experience of several MS4s audited by the Federal Environmental Protection Agency (EPA) over the past 3 years.

| Forms Committee | | | |
|---------------------------|---------------------------------------|--------------------------------------|--|
| John Dzialo | Town of Colonie | Traditional Land Use Control MS4 | |
| Maryella Davenport, CPESC | City of Albany, Albany Water Board* | Traditional Land Use Control MS4 | |
| David Dressel | City of Watervliet* | Traditonal Land Use Control MS4 | |
| David Kubek, CPESC, CPWQC | Albany County | Traditional Non Land Use Control MS4 | |
| Frank Fazio, PE | University at Albany-SUNY | Non-Traditional MS4 | |
| Nancy Heinzen | Stormwater Coalition of Albany County | | |

If you have suggestions for improving this document and related forms and check lists, go the Stormwater Coalition of Albany County website (http://www.stormwateralbanycounty.org/) and submit your comments using the Public Comment portal. Thank you!

| | Table of Contents | |
|---|--|----------|
| Guidance Document Explained an | d Instructions | |
| | Description of the document, it's purpose, organization, and suggestions for use by MS4 staff, SWPPP preparers and reviewers | p.1 |
| Part I. SWPPP Oversight Forms fo | or MS4s | Part I |
| A. Basic Project Information | Place to record basic information used to identify the SWPPP | p.2 |
| B. Permit Coverage Information | Place to track construction activity permit coverage over time; related changes in ownership; permitted land area; status of coverage | p.2 |
| C. Contact Information | Place to record contact information pertaining to all individuals involved with the Construction Activity permit (Owner operator; SWPPP preparer/reviewers/inspectors; MS4 consultants/staff) | p.3 |
| D. SWPPP Reviewers | Place to identify all SWPPP reviewers; submission dates; status of inter-MS4, stakeholder reviews | p.8 |
| E. SWPPP Comments and Corrections | Place for SWPPP reviewers and MS4s to identify and communicate missing SWPPP components and status of corrections | p.10 |
| F. Other Municipal Documents | Place for MS4s to communicate internally the status of municipal permits/documents related to land disturbance and associated development (building permits, fees, escrow accounts, maintenance agreements, deeds, etc.) | p.12 |
| G. Critical Information Summary - From SWPPP - From MS4 | Summary of key project information from SWPPP and/or from MS4. Information is used to determine SWPPP type and necessary design features given site. | p.18 |
| Part II. SWPPP Content Check List - Long Version | | Part II |
| A. Project Parameters | Project location; site regulatory features; local laws; policy documents; physical geography; eligibility for construction activity permit coverage; project type (E/SC only, E/SC-Post Cons) | p.2 |
| B. Forms and Documents | Forms and documentation to submit with SWPPP | p.6 |
| C. Erosion and Sediment Control Components | Required SWPPP content named in Construction Activity Permit GP-0-15-002 and by request from MS4s | p.10 |
| D. Post Construction Stormwater Management Components | Required SWPPP content named in Construction Activity Permit GP-0-15-002; the NYS Stormwater Management Design Manual (2015); and by request from MS4s | p.17 |
| E. Municipal Requirements-Maps, Construction Drawings, Standards | Requirements developed by MS4s to help standardize SWPPP submissions, clarify MS4 expectations, and visualize all phases of the construction project | p.31 |
| Part III. SWPPP Content Check L | ist - Short Version | Part III |
| A. Project Parameters | Same content as Part II.A. (Numbering of line items is the same as Part II. SWPPP Content Check List. Where appropriate, content has been abbreviated. | p.2 |
| B. Forms and Documents | Same content as Part II.B. (see above) | p.4 |
| C. Erosion and Sediment Control Components | Same content as Part II.C. (see above) | p.5 |
| D. Post Construction Stormwater Management Components | Same content as Part II.D. (see above) | p.10 |
| E. Municipal Requirements-Maps, Construction Drawings, Standards | Same content as Part II.E. (see above) | p.19 |

Oversight of the Construction Activity Permit

Guidance Document Explained & Instructions

Purpose

The purpose of this document is to help public entities regulated under the Federal Clean Water Act MS4 Permit, as administered by the New York State Department of Environmental Conservation (NYSDEC), better manage their oversight of the NYSDEC Construction Activity General Permit. It functions as a teaching tool to help explain what should be included in a Construction Activity Storm Water Pollution Prevention Plan (SWPPP) and as a compendium of forms to help MS4s manage the review process and track SWPPP content.

The "forms" presented here were created using Microsoft EXCEL and are available in two formats; as a PDF which includes all forms organized by topic as described in the Table of Contents and as an EXCEL workbook easily adapted to individual MS4 needs and interests.

While the document in total was created by the Stormwater Coalition of Albany County, how individual MS4s choose to use it is at the discretion of the MS4. Specific MS4 instructions can be noted below. In general the intent of this Guidance Document is to establish expectations beneficial to all involved with preparing, reviewing, and implementing SWPPPs.

Part I. SWPPP Oversight Tools for MS4s

This includes a set of forms intended to help MS4s track who is responsible for what regarding the SWPPP review process; the status of corrections and modifications of SWPPPs; the status of construction activity permit coverage over time; the status of internal municipal documents related to land disturbance permitting; and the status of long term maintenance agreements pertaining to post construction stormwater management practices. The Part I. G. Critical Information Summary form is used to record key information about the proposed SWPPP.

Part II. and Part III. SWPPP Content Check Lists – Long and Short Versions

These SWPPP Content Check Lists, both the Long and Short Versions are a comprehensive list of items to include in a SWPPP. They are broken out into topics, each with a specific purpose.

Section A. Project Parameters. Information establishes the type of SWPPP to be prepared, regulatory/MS4 requirements, site geography.

Section B. Forms and Documents. Lists all forms and documents to include with the SWPPP.

Section C. Erosion and Sediment Control Components. Reviewers and Preparers are reminded of required elements named in the NYSDEC Construction Activity Permit GP-0-15-002; MS4s clarify SWPPP requirements and note additonal requests.

Section D. Post Construction Stormwater Management Components. Reviewers and Preparers are reminded of required elements named in the NYSDEC Construction Activity Permit GP-0-15-002 and NYSDEC Stormwater Management Design Manual (2015); MS4s clarify SWPPP requirements and note additional requests.

Section E. Municipal Requirements. Listing of municipal requirements pertaining to drawings, maps, and rainfall standards.

The Long Version is highly descriptive of permit and municipal requirements. This is intentional. The language is there to help explain the content of a SWPPP and serve as guidance for individuals less familiar with SWPPP requirements.

The Short Version is an abbreviated listing of requirements intended to remind experienced SWPPP Preparers and Reviewers of SWPPP requirements.

Individuals new to SWPPP preparation or review may want to use the Long Version Check List, while others more familiar with SWPPPs may want to use it for reference. Both versions use the same number to reference the same check list item. If using the Short Version, that number will refer back to the Long Version where there is a more detailed description. Some items have been removed from the Short Version. This explains gaps in the Short Version numbering system.

Using the SWPPP Content Check Lists. In the **SWPPP Preparer column**, the Preparer notes if the item is present, not applicable, and records where the item is located by page number in the SWPPP. In the **SWPPP Reviewer column**, MS4 staff and/or a consultants hired by the MS4 check the content of the SWPPP against the SWPPP Preparer's information. Items missing from the SWPPP or in need of clarification can then be recorded by the SWPPP Reviewer in the **Part I. SWPPP Oversight Forms for MS4s - E. SWPPP Comments and Corrections form**, tracked by item number and shared with others (SWPPP Preparer, SWPPP Reviewer(s), municipal staff), as needed.

HOW TO USE THESE FORMS & CHECK LISTS: MS4 INSTRUCTIONS TO SWPPP Preparers and/or Reviewers

| CONTENT | | | |
|--|--|-------|--|
| | Part I. SWPPP Oversight Forms for MS4s | | |
| A. Basic Project Information | Place to record basic information used to identify the SWPPP | p.2 | |
| B. Permit Coverage Information | Place to track construction activity permit coverage over time; related changes in ownership; permitted land area; status of coverage | p.2 | |
| C. Contact Information | Place to record contact information pertaining to all individuals involved with the Construction Activity permit (Owner operator; SWPPP preparer/reviewers/inspectors; MS4 consultants/staff) | p.3 | |
| D. SWPPP Reviewers | Place to identify all SWPPP reviewers; submission dates; status of inter-MS4, stakeholder reviews | p.8 | |
| E. SWPPP Comments and Corrections | Place for SWPPP reviewers and MS4s to identify and communicate missing SWPPP components and status of corrections | p.10 | |
| F. Other Municipal Documents | Place for MS4s to communicate internally the status of municipal permits/documents related to land disturbance and associated development (building permits, fees, escrow accounts, maintenance agreements, deeds, etc.) | p.12 | |
| G. Critical Information Summary - From SWPPP - From MS4 | Summary of key project information from SWPPP and/or from MS4. Information is used to determine SWPPP type and necessary design features given site. | p. 18 | |

| Part I. SWPPP Oversight | t Forms for MS4s A. Basi | c Project Informatior | B. Permit Coverage Info | rmation | |
|---|---|--|--|--|--|
| A. Basic Project Informa | tion | | | | |
| Project Name: | | Site Address: | | | |
| | | | | | |
| Project Owner or Operator | : | | Location of Project (name of municipalit(ies); nearest cross streets) | | |
| Date Project Submitted Fo | r Paviaw: | | If project requires SWPPP re | wiew by an MS4 name of | |
| Date Project Submitted Po | r Keview. | | If project requires SWPPP review by an MS4, name of MS4/municipality: | | |
| | | | SPDES MS4 Permit No. of MS4/Municipality: | | |
| # of Acres To Be Disturbed: | | | Project identifier used by MS4 to manage project, if available (GIS ID number; spreadsheet ID, etc.): | | |
| B. Permit Coverage Info | rmation (For MS4 Staff) | | | | |
| If project receives Constr | ruction Activity permit cov | erage | | | |
| Construction SPDES Perm | it No: | | Date SPDES Coverage Authorized (date stamp of Acknowledgment Letter from NYSDEC): | | |
| For projects which requi | red review by Town, Villag | ge or City | | | |
| MS4 Official who signed MS4 SWPPP Acceptance MS4 Off | | Form/Date MS4 Official signed form: Terminated (date stam | | Date SPDES Coverage Terminated (date stamp of Ack. Letter from NYSDEC): | |
| When project ownership | changes | | | | |
| and specification, the origi coverage by submitting a N the original owner or opera new owner or operator to the | nal owner or operator must n Notice of Intent (NOI) with th ator shall then submit a comp | notify the new owner or ne Department (NYSD pleted Notice of Termir is in Part II.A.1 of this p | r operator, in writing of the red EC). Once the new owner or operation with the name and permover mit. If the original owner or | rol over the construction plans quirement to obtain permit operator obtains permit coverage, it identification number of the operator maintains ownership of | |
| Continuing Owner or Operator/Existing SPDES Permit No. | New Owner-Operator or Owner-Operator(s) if land area sub-divided. | New SPDES Permit No. | Date SPDES Coverage Authorized (date stamp of Acknowledgment Letter from NYSDEC) | Date SPDES Coverage Terminated (date stamp of of Acknowledement Letter from NYSDEC) | |
| | | | | | |
| | | | | | |
| | | | | | |

| Part I. SWPPP Oversight Forms for MS4s C. Contact Information | | | |
|---|-------------------|--|--|
| 1. Owner Operator Information | | | |
| a. Project Owner or Operator (Applicant) | | | |
| First Name: | Last Name: | | |
| Mailing Address | | | |
| Street: | | | |
| Street: | | | |
| City, State, Zip Code: | | | |
| Phone Number: | Email: | | |
| b. Project Engineer (All Aspects of Project) TYPICAL FO | PR LARGE PROJECTS | | |
| First Name: | Last Name: | | |
| Company Name: | | | |
| Mailing Address | | | |
| Street: | | | |
| Street: | | | |
| City, State, Zip Code: | | | |
| Phone Number: | Email: | | |
| c. SWPPP Preparer (Company) | | | |
| Name of Company: | | | |
| Mailing Address | | | |
| Street: | | | |
| Street: | | | |
| City, State, Zip Code: | | | |
| none Number: Email: | | | |

| Part I. SWPPP Oversight Forms for MS4s C. Contact Information | | | |
|--|--|--|--|
| d. SWPPP Preparer (Individual) | | | |
| First Name: | Last Name: | | |
| Mailing Address | | | |
| Street: | | | |
| Street: | | | |
| City, State, Zip Code: | | | |
| Phone Number: | Email: | | |
| SWPPP Preparer Credentials (circle all that apply): Professiona | al Engineer (PE); Registered Landscape Architect | | |
| (RLA); Certified Professional in Erosion and Sediment Contro | l (CPESC) | | |
| If SWPPP Includes Post Construction Practices: | | | |
| Name of Qualified Professional: | | | |
| Credentials of Qualified Professional : | | | |
| Role of Qualified Professional (circle one): Prepare SWPPP; S | Supervises SWPPP Preparer | | |
| e. SWPPP Inspector for Owner or Operator (Individual) - | ANTICIPATED | | |
| First Name: | Last Name: | | |
| Company Name: | | | |
| Mailing Address | | | |
| Street: | | | |
| Street: | | | |
| City, State, Zip Code: | | | |
| Phone Number: | Email: | | |
| If SWPPP requires Qualified Inspector*, Qualified Inspector credentials (circle all that apply): | | | |
| Professional Engineer (PE); Registered Landscape Architect (RLA); Certified Professional in Erosion & Sediment | | | |
| Control (CPESC); Trained Contractor w/4 Hr E/SC training working under direct supervision of PE or RLA. | | | |
| If Trained Contractor, name of supervising PE or RLA: | | | |
| If SWPPP does NOT require Qualified Inspector, SWPPP Inspector credentials (circle all that apply): | | | |
| Professional Engineer (PE); Registered Landscape Architect (RLA); Certified Professional in Erosion and | | | |
| Sediment Control (CPESC); Trained Contractor w/4 Hr E/SC; Other (describe) | | | |

*See criteria for needing a *Qualified Inspector* in Part IV.C.1. of GP-0-15-002 (pg. 25)

| Part I. SWPPP Oversight Forms for MS4s C. Contact Information | | | |
|---|---|--|--|
| 2. MS4 Oversight of Construction Activity Permit | | | |
| a. SWPPP Reviewer (Individual) | | | |
| Role (circle all that apply): Consultant Hired By MS4; MS4 St | aff Person | | |
| Other Interested Party (circle all that apply): County 239 Revie | ew; Other Stakeholder (MS4); Other | | |
| First Name: | Last Name: | | |
| Company Name: | | | |
| Mailing Address | | | |
| Street: | | | |
| Street: | | | |
| City, State, Zip Code: | | | |
| Phone Number: | Email: | | |
| SWPPP Reviewer credentials (circle all that apply): Profession | al Engineer (PE); Registered Landscape Architect | | |
| (RLA); Certified Professional in Erosion & Sediment Control (| (CPESC); Trained Contractor (4 Hr E/SC Training); | | |
| Other (describe) | | | |
| b. SWPPP Reviewer (Individual) - ADDITIONAL | | | |
| Role (circle all that apply): Consultant Hired By MS4; MS4 St | aff Person | | |
| Other Interested Party (circle all that apply): County 239 Revie | ew; Other Stakeholder (MS4); Other | | |
| First Name: | Last Name: | | |
| Company Name: | | | |
| Mailing Address | | | |
| Street: | | | |
| Street: | | | |
| City, State, Zip Code: | | | |
| Phone Number: | Email: | | |
| SWPPP Reviewer Credentials (circle all that apply): Professional Engineer (PE); Registered Landscape Architect | | | |
| (RLA); Certified Professional in Erosion and Sediment Control (CPESC); Trained Contractor (4 Hr E/SC Training); | | | |
| Other (describe) | | | |

| Part I. SWPPP Oversight Forms for MS4s C. Contact Information | | | |
|--|--|--|--|
| c. MS4 Stormwater Program Staff Person (Individual) | | | |
| Role (circle all that apply): Stormwater Program Coordinator; Stormwater Management Officer | | | |
| Other (describe) | | | |
| First Name: | Last Name: | | |
| MS4/Institution Name: | | | |
| Mailing Address | | | |
| Street: | | | |
| Street: | | | |
| City, State, Zip Code: | | | |
| Phone Number: | Email: | | |
| MS4 Staff Credentials (circle all that apply): Professional Engi | ineer (PE); Registered Landscape Architect (RLA) | | |
| Certified Professional in Erosion and Sediment Control (CPES | C); Trained Contractor (4 Hr E/SC Training); | | |
| Code Enforcement Officer (CEO); Other (describe) | | | |
| | | | |
| d. SWPPP Site Inspector for MS4 (Individual) - ANTICIP. | ATED | | |
| Role (circle all that apply): Consultant Hired By MS4; MS4 St | aff Person; SWCD Staff; Others (describe) | | |
| First Name: | Last Name: | | |
| Company/MS4 Institution Name: | | | |
| Mailing Address | | | |
| Street: | | | |
| Street: | | | |
| City, State, Zip Code: | | | |
| Phone Number: | Email: | | |
| SWPPP MS4 Inspector Credentials (circle all that apply): Professional Engineer (PE); Registered Landscape | | | |
| Architect (RLA); Certified Professional in Erosion and Sediment Control (CPESC); Trained Contractor (4 Hr E/SC | | | |
| Training); Code Enforcement Officer (CEO); Other (describe) | | | |
| | | | |

| Part I. SWPPP Oversight Forms for MS4s C. Contact Information | | | |
|---|------------|--|--|
| e. SWPPP Enforcement - SW Management Officer for MS4 (Individual) - ANTICIPATED | | | |
| First Name: | Last Name: | | |
| MS4/Institution Name: | | | |
| Mailing Address | | | |
| Street: | | | |
| Street: | | | |
| City, State, Zip Code: | | | |
| Phone Number: Email: | | | |
| SWPPP Management Officer Credentials (circle all that apply): Professional Engineer (PE); | | | |
| Certified Professional in Erosion and Sediment Control (CPESC); Registered Landscape Architect (RLA); | | | |
| Trained Contractor (4 Hr E/SC Training); Code Enforcement Officer (CEO); Other (describe) | | | |
| | | | |

Date:____

Part I. SWPPP Oversight Forms for MS4s D. SWPPP Reviewers

1. MS4 is not the owner or operator of the project, but as a Traditional MS4 w/Land Use Control (Town, Village, City), the MS4 oversees the Construction Activity Permit. MS4 SWPPP Acceptance Form is required and is submitted by the developer with the Construction Activity Permit Notice of Intent.

Date of Submission:

Name of Company and/or Individual submitting the SWPPP for review by a Traditional Land Use Control MS4:

Name of Individual from MS4 who received SWPPP:

Name of Individual from MS4 Responsible for Coordinating SWPPP review:

2. MS4 is the owner or operator of project

a. MS4 owns property, but as a Traditional MS4 w/ No Land Use Control (County) or Non Traditional MS4 (Public University), procedures exist to ensure MS4 Permit compliant oversight of the Construction Activity. MS4 SWPPP Acceptance Form is <u>not</u> required.

Name of consulting firm and/or individual who prepared SWPPP:

Are SWPPPs reviewed by others from MS4, Y/N? (If unclear, see County or Public University procedures)

If Yes, name of Individual who received the SWPPP for review:

If others review SWPPP, name of individual from MS4 responsible for coordinating internal SWPPP review:

Date SWPPP first provided to others for review:

b. MS4 owns property. SWPPP review, approval, and inspection requirements are embedded in procedures for municipal owned projects. MS4 SWPPP Acceptance Form is <u>not</u> required.

Name of consulting firm and/or individual who prepared SWPPP:

Are SWPPPs reviewed by others from MS4, Y/N?

If Yes, name of Individual who received the SWPPP for review:

If others review SWPPP, name of individual from MS4 responsible for coordinating internal SWPPP review:

Date SWPPP first provided to others for review:

Part I. SWPPP Oversight Forms for MS4s D. SWPPP Reviewers

Project:____ Date:__

Part I. SWPPP Oversight Forms for MS4s D. SWPPP Reviewers 3. Other Reviewers (County, Other Stakeholders) Does this project potentially impact County infrastructure, other MS4/municipalities, or other stakeholders, Y/N? If Yes, list of others to review SWPPP; contact information, comments, and actions taken. a. Name of Institution/Stakeholder Contact Name Comments Actions Taken Email Phone b. Name of Institution/Stakeholder Contact Name Comments Actions Taken Email Phone c. Name of Institution/Stakeholder Contact Name Comments Actions Taken Email Phone d. Name of Institution/Stakeholder Actions Taken Contact Name Comments Email Phone

| Part I. SWPPP Oversight Forms for MS4s E. SWPPP Comments and Corrections | | | |
|--|---|----------|-----------------|
| 1. First Submission for Review | | | |
| Name/Title of Reviewer: | | | |
| Date | Issues By Item & Page Number (For Item/Pg #, see Part II & III Ck Lists) | Comments | Corrected, Y/N? |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| 2. Second Submission for Review Name/Title of Reviewer: | | | |
| Date | Issues By Item & Page Number (For Item/Pg #, see Part II & III Ck Lists) | Comments | Corrected, Y/N? |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Part I. SWPPP Oversight Forms for MS4s E. SWPPP Comments and Corrections 3. Third Submission for Review Name/Title of Reviewer: Date Issues By Item & Page Number Comments Corrected, Y/N? (For Item/Pg #, see Part II & III Ck Lists) 4. Fourth Submission for Review Name/Title of Reviewer: Issues By Item & Page Number Date Corrected, Y/N? Comments (For Item/Pg #, see Part II & III Ck Lists)

Project:_____

| Part I. SWPI | I. SWPPP Oversight Forms for MS4s F. Other Municipal Documents | | | | | | | | | | | | | | | | | | | |
|---|--|---------------------------------|-----------------|-------------------------------|----------|--|-------|------------------|--------------------|-------------------------|--------------|---------------------|-------------------------|--------------|--------------------|-------------------------|-------|--------------|------------------------|-------------------------|
| | | Owner | or operator | | | | | | | | MS | 4/Munic | ipal Ove | rsight | | | | | | |
| List of | Construction | Activity Pern | nit No.: | | | | | | | | Nam | e of MS4 | 4/Munic | ipality: | | | | | | |
| Documents | Date SPDES | Permit Issued | l*: | | | | | | | | | | | -F) . | | | | | | |
| | *SPDES Permit co | overage is required | d BEFORE land | disturbance car | ı begin. | | - | | | | 1 | | | 1 | | | n | | | |
| Description | ☑, Informed By MS4 That Document, | ☑, Doc- Application- Fees | ⊠, Pmt Rec'd | Ø, Doc Final- Executed- | ⊠, | ⊠, MS4 Informs Owner Operator Of | | pp-Fees By Wh | | | | Issued (om, Dat | | | Termina Vhom, D | | | | cuted-Iss n, Date ? | |
| Description | Permit, Fees Required (Date?) | Submtted to MS4 (Date?) | (Date?) | Issued (Date?) | NA | Required Documents, Permits, Fees (Date?) | Ø, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | ⊠, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal |
| Stormwater NYSDEC SPDES Permits | | | | | | | | | | | | | | | | | | | | |
| Construction Activity Permit | | | | | | | | | | | | | | | | | | | | |
| MS4 SWPPP Acceptance Form | | | | | | | | | | | | | | | | | | | | |
| Notice of Termination Form (signed by MS4) | | | | | | | | | | | | | | | | | | | | |
| Multi -Sector General Permit | | | | | | | | | | | | | | | | | | | | |
| Municipal Permits | | | | | | | | | | | | | | | | | | | | |
| Building Permit | | | | | | | | | | | | | | | | | | | | |
| Grading Permit | | | | | | | | | | | | | | | | | | | | |

Project:_____

| Part I. SWPF | PP Oversight | Forms for M | S4s F. Oth | ner Municij | pal Do | cuments | | | | | | | | | | | | | | |
|---|-------------------------------|-------------------------|---|------------------|--------------|----------------------------|-------------------------|------------------|--------------------|-------------------------|--------------|---------------------|-------------------------|----------|--------------------|--------------------|-------------------------|--|------------------------|--|
| | | Owner | or operator | | | | | | | | MS | 4/Munic | ipal Ove | ersight | | | | | | |
| List of | Construction | Activity Pern | nit No.: | | | | | | | | Nam | e of MS | 4/Munic | ipality: | | | | | | |
| Documents | Date SPDES | Permit Issued | *: | | | • | | | | | | | | 1 | | | | | | |
| | *SPDES Permit co | overage is required | d BEFORE land | disturbance can | ı begin. | | - | | | | | | | | | | | | | |
| | ☑, Informed By MS4 That | ☑, Doc- Application- | ⊠, Pmt | ⊠, Doc Final- | | ☑, MS4 Informs Owner | | pp-Fees By Wh | | | | Issued (om, Dat | | | Termina Vhom, D | | | | cuted-Iss n, Date ? | |
| Description | Ion Document Rec'd Executed ' | ⊠, NA | Operator Of Required Documents, Permits, Fees (Date?) | Ø, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Ø, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal | | | |
| Clearing Permit | | | | | | | | | | | | | | | | | | | | |
| Clearing & Grading Permit | | | | | | | | | | | | | | | | | | | | |
| Demolition Permit | | | | | | | | | | | | | | | | | | | | |
| Highway Work Permit (Municipal) | | | | | | | | | | | | | | | | | | | | |
| Utility Permit (Water Supply) | | | | | | | | | | | | | | | | | | | | |
| Utility Permit (Sanitary) | | | | | | | | | | | | | | | | | | | | |
| Utility Permits (Storm) | | | | | | | | | | | | | | | | | | | | |
| Watercourses and Flood Plain Permit | | | | | | | | | | | | | | | | | | | | |
| Street Opening Permit | | | | | | | | | | | | | | | | | | | | |

Project:_____

| Part I. SWPI | t I. SWPPP Oversight Forms for MS4s F. Other Municipal Documents | | | | | | | | | | | | | | | | | | | |
|--|--|---|---------------|------------------|--------------------|----------------------------|--------------|--------------------|-------------------------|--------------|--------------------|-------------------------|----------|--------------|--------------------|-------------------------|--|--|------------------------|--|
| | | Owner | or operator | | | | | | | | MS | 4/Munic | ipal Ove | rsight | | | | | | |
| List of | Construction | Activity Pern | nit No.: | | | | | | | | Nam | e of MS4 | 4/Munic | ipality: | | | | | | |
| Documents | Date SPDES | Permit Issued | l*: | | | | | | | | | | | 1 5 | | | | | | |
| | *SPDES Permit co | overage is required | d BEFORE land | disturbance car | ı begin. | | | | | | | | | | | | | | | |
| | ☑, Informed By MS4 That | ☑, Doc- Application- | ⊠, Pmt | ⊠, Doc Final- | | ⊠, MS4 Informs Owner | | | Rec'd B om, Date | | | : Issued (iom, Dat | | | Termina Vhom, D | | | | cuted-Iss n, Date ? | |
| Description | | Operator Of Required Documents, Permits, Fees (Date?) | ⊠, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | ⊠, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal | | | | |
| Other Documents (Not Permits) | | | | | | | | | | | | | | | | | | | | |
| Escrow account | | | | | | | | | | | | | | | | | | | | |
| Deed | | | | | | | | | | | | | | | | | | | | |
| Stormwater Maintenance Agreement | | | | | | | | | | | | | | | | | | | | |
| Certificate of Occupancy | | | | | | | | | | | | | | | | | | | | |
| NFIP Elevation Certificate | | | | | | | | | | | | | | | | | | | | |

Project:_____

| Part I. SWPI | PP Oversight | Forms for M | S4s F. Otl | her Municij | pal Do | cuments | | | | | | | | | | | | | | |
|--|-------------------------------|-------------------------|---|------------------|--------------|----------------------------|-------------------------|--------------|---------------------|-------------------------|--------------|----------------------|-------------------------|----------|--------------------|--------------------|---------------------------------------|--|------------------------|--|
| | | Owner | or operator | | | | | | | | MS | 4/Munic | ipal Ove | ersight | | | | | | |
| List of | Construction | Activity Pern | nit No.: | | | | | | | | Nam | e of MS | 4/Munic | ipality: | | | | | | |
| Documents | Date SPDES | Permit Issued | ! *: | | | | | | | | | | | | | | | | | |
| | *SPDES Permit co | werage is require | d BEFORE land | disturbance can | ı begin. | | _ | | | | 1 | | | 1 | | | · · · · · · · · · · · · · · · · · · · | | | |
| | ☑, Informed By MS4 That | ☑, Doc- Application- | ⊠, Pmt | ⊠, Doc Final- | | ☑, MS4 Informs Owner | | | Rec'd B om, Date | | | t Issued nom, Dat | | | Termina Vhom, D | | | | cuted-Iss n, Date ? | |
| Description | | ⊠, NA | Operator Of Required Documents, Permits, Fees (Date?) | Ø, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Ø, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal | | | |
| Municipal Fees | | | | | | | | | | | | | | | | | | | | |
| Permit Applications | | | | | | | | | | | | | | | | | | | | |
| Building | | | | | | | | | | | | | | | | | | | | |
| Demolition, Clearing, or Grading | | | | | | | | | | | | | | | | | | | | |
| Watercourses and Flood Plain | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| Land Use Review Fees | | | | | | | | | | | | | | | | | | | | |
| Commercial Site Review Fee | | | | | | | | | | | | | | | | | | | | |
| Residential Subdivisions | | | | | | | | | | | | | | | | | | | | |
| Commercial Subdivision | | | | | | | | | | | | | | | | | | | | |

Project:_____

| Part I. SWPI | SWPPP Oversight Forms for MS4s F. Other Municipal Documents | | | | | | | | | | | | | | | | | | | |
|---|---|---|---------------|------------------|--------------------|----------------------------|--------------|--------------------|-------------------------|--------------|--------------------|-------------------------|----------|--------------|--------------------|-------------------------|--|--|------------------------|--|
| | | Owner | or operator | | | | | | | | MS | 4/Munic | ipal Ove | rsight | | | | | | |
| List of | Construction | Activity Pern | nit No.: | | | | | | | | Nam | e of MS4 | 4/Munic | ipality: | | | | | | |
| Documents | Date SPDES | Permit Issued | *: | | | | | | | | | | | 1 2 | | | | | | |
| | *SPDES Permit co | verage is required | d BEFORE land | disturbance car | ı begin. | | - | | | | | | | | | | | | | |
| | ☑, Informed By MS4 That | ☑, Doc- Application- | ⊠, Pmt | ⊠, Doc Final- | | ⊠, MS4 Informs Owner | | | Rec'd B om, Date | | | : Issued (iom, Dat | | | Termina Vhom, D | | | | cuted-Iss n, Date ? | |
| Description | btion Document, Permit, Fees Required (Date?) | Operator Of Required Documents, Permits, Fees (Date?) | ⊠, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | ⊠, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal | | | | |
| Highway and Utility Extension Fee | | | | | | | | | | | | | | | | | | | | |
| SEQR Review | | | | | | | | | | | | | | | | | | | | |
| Rezoning Review | | | | | | | | | | | | | | | | | | | | |
| Watercourses and Flood Plain Application Fees | | | | | | | | | | | | | | | | | | | | |
| Open Development Review Fee | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |

Project:_____

| PP Oversight | Forms for M | S4s F. Otl | her Municij | pal Do | cuments | | | | | | | | | | | | | | |
|---|--|---|---|---|--|--|--|---|---|--|---|---|---|---|---|--|--|---|---|
| | Owner | or operator | | | | | | | | MS | 4/Munic | ipal Ove | rsight | | | | | | |
| Construction | Activity Pern | nit No.: | | | | | | | | Nam | e of MS4 | 4/Munic | ipality: | | | | | | |
| Date SPDES | Permit Issued | l*: | | | | | | | | | | | | | | | | | |
| *SPDES Permit co | werage is required | d BEFORE land | disturbance can | ı begin. | | | | | | 1 | | | | | | 1 | | | |
| ☑, Informed By MS4 That | | Pmt | ☑, Doc Final- | | ⊠, MS4 Informs Owner | | | | | | | | | | | | | | |
| btion Document, Permit, Fees Submtted to MS4 (Date?) [Submt Primate] ☑, NA [Submt Primate] ☑, | Required | Ø, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Bldg Dept | SW Prog Coor | Chief Exec, Legal | Ø, NA | Bldg Dept | SW Prog Coor | Chief Exec, Legal | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | Construction Date SPDES *SPDES Permit co Ø, Informed By MS4 That Document, Permit, Fees Required | Owner Construction Activity Perm Date SPDES Permit Issued *SPDES Permit coverage is required Ø, Informed By MS4 That Document, Permit, Fees Required | Owner or operator Construction Activity Permit No.: Date SPDES Permit Issued*: *SPDES Permit coverage is required BEFORE land Ø, Informed By MS4 That Document, Permit, Fees Required (Date?) | Owner or operator Construction Activity Permit No.: Date SPDES Permit Issued*: *SPDES Permit coverage is required BEFORE land disturbance car Ø, Informed By MS4 That Document, Permit, Fees Required Ø, Doc- Application- Fees Submtted to MS4 (Date?) Ø, Pmt Rec'd Issued (Date?) Ø, Doc Final- Executed- Issued (Date?) | Owner or operator Construction Activity Permit No.: Date SPDES Permit Issued*: *SPDES Permit coverage is required BEFORE land disturbance can begin. Ø, Informed By MS4 That Document, Permit, Fees Required Ø, Doc- Application- Fees Submtted to MS4 (Date?) Ø, Doc Final- Executed- Issued (Date?) Ø, Doc Final- Executed- Issued (Date?) | Construction Activity Permit No.: Date SPDES Permit Issued*: *SPDES Permit coverage is required BEFORE land disturbance can begin. Ø, Informed By MS4 That Document, Permit, Fees Required (Date?) Ø, Doc- Application- Fees Ø, Pmt Rec'd (Date?) Ø, Doc- Final- Executed- Issued (Date?) Ø, MS4 Informs Owner | Owner or operator Construction Activity Permit No.: Date SPDES Permit Issued*: *SPDES Permit coverage is required BEFORE land disturbance can begin. Ø, Informed By MS4 That Document, Permit, Fees Required (Date?) Ø, Doc- Application Fees Ø, Pmt Rec'd (Date?) Ø, Pmt Rec'd (Date?) Ø, Doc- Final- Executed- Issued (Date?) Ø, MS4 Informs Owner Doc-A (Ø | Owner or operator Construction Activity Permit No.: Date SPDES Permit Issued*: *SPDES Permit coverage is required BEFORE land disturbance can begin. Ø, Informed By MS4 That Document, Permit, Fees Required (Date?) Ø, Doc- Application Fees Submtted to MS4 (Date?) Ø, Pmt Rec'd (Date?) Ø, Doc- Final- Executed- Issued (Date?) Ø, MS4 Informs Owner Operator Of Required Documents, Permits, Fees Doc-App-Fees (Ø By Wh | Owner or operator Construction Activity Permit No.: Date SPDES Permit Issued*: *SPDES Permit coverage is required BEFORE land disturbance can begin. Ø, Informed By MS4 That Document, Permit, Fees Required (Date?) Ø, Doc- Application Fees Submtted to MS4 (Date?) Ø, Pmt Rec'd (Date?) Ø, Doc- Final- Executed- Issued (Date?) Ø, MS4 Informs Owner Doc-App-Fees Rec'd B (Ø, MS4 Informs Owner Ø, Informed By MS4 (Date?) Ø, Pmt Rec'd (Date?) Ø, Doc Final- Executed- Issued (Date?) Ø, MS4 Informs Owner Doc-App-Fees Rec'd B (Ø By Whom, Date Operator Of Required Documents, Permits, Fees | Owner or operator Construction Activity Permit No.: Date SPDES Permit Issued*: *SPDES Permit coverage is required BEFORE land disturbance can begin. Ø, Informed By MS4 That Document, Permit, Fees Required (Date?) Ø, Doc- Application Fees Submtted to MS4 (Date?) Ø, Pmt Rec'd (Date?) Ø, Doc- Final- Executed- Issued (Date?) Ø, MS4 Informs Owner Doc-App-Fees Rec'd By MS4 (Ø By Whom, Date ?) Ø, Informed By MS4 (Ø By Whom, Date ?) Ø, NA Bldg Dept SW Prog Coor | Owner or operator MS Construction Activity Permit No.: MS Date SPDES Permit Issued*: Name *SPDES Permit coverage is required BEFORE land disturbance can begin. MS4 Ø, Informed By MS4 Ø, Doc-Application Fees Math Document, Permit, Fees Submitted to MS4 (Date?) Ø, Date?) | Owner or operator MS4/Munic Construction Activity Permit No.: Image: Second | Owner or operator MS4/Municipal Ove Construction Activity Permit No.: Name of MS4/Municipal Ove Date SPDES Permit Issued*: ** *SPDES Permit coverage is required BEFORE land disturbance can begin. Image: Construction Activity Permit Issued*: Image: MS4/Municipal Overage is required BEFORE land disturbance can begin. Image: Construction Activity Permit Issued*: Image: MS4 By MS4 That Document, Permit, Fees Rec'd By MS4 (Date?) Image: Construction Activity Permit Issued (Image: Construction Activity Permit, Fees Rec'd By MS4 (Image: Construction Activity Permit Issued (Image: Construction Activity Permit, Fees Rec'd By MS4 (Image: Construction Activity Permit Rec'd (Image: Construction Activity Permit, Fees Rec'd By MS4 (Image: Construction | Owner or operator MS4/Municipal Oversight Construction Activity Permit No.: Image: Second | Owner or operator MS4/Municipal Oversight Construction Activity Permit No.: Image: Second | Owner or operator MS4/Municipal Oversight Construction Activity Permit No.: Name of MS4/Municipality: Date SPDES Permit Issued*: ** **SPDES Permit coverage is required BEFORE land disturbance can begin. Ø, Informed Ø, Informed Ø, Doc- By MS4 Ø, Doc- That Ø, Doc- Document, Ø, Permit Permit, Fees Ø, Doc- Submtted Image: Comparison of the main second of the main | Owner or operator MS4/Municipal Oversight Construction Activity Permit No.: Image: SepDes Permit Issued*: Date SPDES Permit Issued*: Image: SepDes Permit Coverage is required BEFORE land disturbance can begin. Image: MS4/Municipal Oversight Image: SepDes Permit Coverage is required BEFORE land disturbance can begin. Image: MS4/Municipal Oversight Image: SepDes Permit Coverage is required BEFORE land disturbance can begin. Image: MS4/Municipal Oversight Image: SepDes Permit Coverage is required BEFORE land disturbance can begin. Image: MS4/Municipal Oversight Image: SepDes Permit Coverage is required BEFORE land disturbance can begin. Image: MS4/Municipal Oversight Image: SepDes Permit Coverage is required BEFORE land disturbance can begin. Image: MS4/Municipal Oversight Image: SepDes Permit Coverage is required BEFORE land disturbance can begin. Image: MS4/Municipal Oversight Image: SepDes Permit Coverage is required BEFORE land disturbance can begin. Image: MS4/Municipal Oversight Image: SepDes Permit Coverage is required BEFORE land disturbance can begin. Image: MS4/Municipal Oversight Image: SepDes Permit Coverage is required BEFORE land disturbance can begin. Image: MS4/Municipal Oversight Image: SepDes Permit Coverage is required BEFORE land disturbance can begin. Image: MS4/Municipal Oversight Image: SepDes Permit Coverage is required | Owner or operator MS4/Municipal Oversight Construction Activity Permit No.: Name of MS4/Municipality: Date SPDES Permit Issued*: Name of MS4/Municipality: *SPDES Permit coverage is required BEFORE land disturbance can begin. Image: Coverage is required BEFORE land disturbance can begin. Ø, Informed By MS4 That Document, Permit, Fees Rec'd By MS4 (Date?) Ø, Proteon (Date?) Image: Coverage is required BEFORE land disturbance can begin. Ø, Informed Document, Permit, Fees Rec'd By MS4 (Date?) Ø, MS4 (Date?) Ø, MS4 (Date?) Ø, MS4 (Date?) Ø, MS4 (Date?) Doc-App-Fees Rec'd By MS4 (Imforms Owner Permit Issued (Image: Barbon (Date Required Documents, Permits, Fees Rec'd By MS4 (Date?) Permit Terminated (Image: Barbon (Date Required Documents, Permits, Fees Rec'd By MS4 (Date?) Permit State (Date Required Documents, Permits, Fees Rec'd By MS4 (Date?) Permit State (Date Required Documents, Permits, Fees Rec'd By MS4 (Date?) Prog Exec, Doc Required Documents, Prog Exec, Rec'd By MS4 (Date Required Documents, Permits, Fees Rec'd Rec'd Required Documents, Permits, Fees Rec'd | Owner or operator MS4/Municipal Oversight Construction Activity Permit No.: Image: Second |

| . SWPPP Oversight Forms for MS4s | | | | | | | | | |
|---|--|---|--|--|--|--|--|--|--|
| G. Critical Information Sum | mary - From SWPPP - F | rom MS4 (I Check All That Apply; Provide Info Where Indicated) | | | | | | | |
| | | MS4/Municipality | | | | | | | |
| 1. Project Owner | | Project NOT owned by MS4, but is located in an MS4 municipality with land use control (town-village-city) | | | | | | | |
| | | Project NOT owned by MS4, NOT located in an MS4 municipality | | | | | | | |
| 2. Private Developer Projects F | Reviewed by MS4 | | | | | | | | |
| a. Local Law by number and oversight of Construction Ac this project | | 2.a | | | | | | | |
| b. Land disturbance threshold feet) adopted by MS4 and ind triggers ovesight of land dist | cluded in local law which | 2.b | | | | | | | |
| c. Municipal laws-codes-ord: to support use of green infras remove obstacles for develop | structure practices and | 2.c | | | | | | | |
| d. Policies adopted by MS4 t infrastructure practices and r developers | | 2.d | | | | | | | |
| e. If MS4 owns storm water i discharges to an impaired wa Appendix 2 of the MS4 pern additional MS4 requirements management practices design requirements. | terbody segment listed n nit, there may be s related to stormwater | 2.e | | | | | | | |
| 3. Municipal Permits; Other Pu | ublic Entity Permits Policy | Documents | | | | | | | |
| a. Permits owner-operator mu disturbance can begin (ex. B Clearing; Grubbing; Demolit Activity Permit; Other) | uilding; Grading; | 3.a | | | | | | | |
| b. Policy and/or procedures of MS4 for MS4 owned constru support use of green infrastru better management of constru | action projects intended to acture and encourage | 3.b | | | | | | | |
| 4. Municipalities with CSO an | d MS4 SPDES Permits | | | | | | | | |
| a. Albany Pool CSO LTCP F requirements which impact d practices in areas with storm (construction activity may di and/or combined storm- sanit | esign of stormwater system infrastructure scharge to storm only | 4 | | | | | | | |
| | | Total site area (acres): | | | | | | | |
| 5. Site Disturbance | | Total disturbed area (acres): (total disturbance includes entire common plan of development) | | | | | | | |
| | | Total area not disturbed (acres): | | | | | | | |

| I. SWPPP Oversight Forms f | or MS4s | | |
|---|-------------------------|--|--|
| G. Critical Information Sum | mary - From SWPPP | - From MS4 (Check All Th | at Apply; Provide Info Where Indicated) |
| | | Erosion and Sediment Controls Only (formerly refered to as "BASIC" SWPPP) | Why E-SC only project? List relevant Construction Activity Permit Appendix B Table 1 Activity. Include all that apply. |
| 6. Project Type | | Erosion and Sediment Controls AND Post Construction Stormwater Management Practices (formerly refered to as "FULL" SWPPP) | Why E-SC with post-construction practices project? List relevant Construction Activity Permit Appendix B Table 2 Activity. Include all that apply |
| | | New Development | 1 |
| 7. Project Activity Type (Post | | New Development in Enhar | nced Phosphorus Removal Watershed |
| Construction Stormwater Practices) | | Redevelopment Activity | |
| Tractices) | | Redevelopment Activity and | d New Development |
| 8. Receiving Waters of Constru | ction Activity discharg | _ | • |
| | | Class C (T) or Class C (TS) | "Trout waters" |
| a. Stream classification of | | Class AA or AA-s; and b "I | Drinking water" |
| receiving water | | Other | |
| h Degulatory status | | | |
| b. Regulatory status | | | |
| i. Receiving water is an | | Y, Ann Lee (Shakers) Pond | , Stump Pond |
| impaired 303 (d) segment | | Y, Basic Creek Reservoir | |
| listed in Appendix E of Contruction Activity Permit, Y/N? | | No | |
| ii. Receiving water is an | | Y. Ann Lee (Shakers) Pond Phosphorus | , Stump Pond. Primary Pollutand of Concern: |
| impaired 303 (d) segment listed in Appendix 2 of | | Y. Basic Creek reservoir. Pr | rimary Pollutand of Concern: Phosphorus |
| MS4 Permit | | No | |
| ii. Receiving water is an | | Y. Name of waterbody: | |
| impaired 303 (d) segment | | No | |
| | | First order | |
| iii. Stream order of initial | | Second order | |
| receiving water (from | | Third order | |
| NHDPlus dataset) | | Fourth order | |
| | | Fifth order (Cpv doesn't app | bly) |
| d. Does site discharges | | Yes, discharges to tidal wate | |
| directly to tidal water? | | No, does NOT discharge to | tidal water |

I. SWPPP Oversight Forms for MS4s G. Critical Information Summary - From SWPPP - From MS4 (I Check All That Apply; Provide Info Where Indicated) 9. Storm system infrastructure Private owner Public storm system, owned by MS4. Name of MS4(s): a. If Construction Activity Permit discharges are Publically owned system, not an MS4. Name of owner: conveyed to another storm system, who owns that system? Combined sanitary/storm system owned by municipalty with MS4 & CSO Permit. Early stages of project, discharges may go to a combined sanitary/storm system; by the end of the project, discharges to a separated system. Private owner Public storm system, owned by MS4. Name of MS4(s): b. If area of the construction activity receives stormwater runoff, who owns the sending storm system? Publically owned system, not an MS4. Name of owner: 10. Site Conditions HSG A HSG B HSG C HSG D a. Hydrological soil groups (HSG) present at site HSG A/D* HSG B/D* HSG C/D* *first letter drained conditions/second letter undrained conditions Highly erodible soils present Moderately erodible soils present b. Soil erodibility Minimal erodible soils present Karst bedrock present c. Karst topography Karst bedrock NOT present Construction activity where map unit Soil Slope Phase identified as E or F (USDA Soil Survey for Albany County) and no existing impervious cover Construction activity where map unit is inclusive of 25% or greater slope (USDA d. Slopes Soil Survey for Albany County) Slopes between 0% and 15%

| I. SWPPP Oversight Forms f | or MS4s | |
|---|------------------|---|
| G. Critical Information Sum | mary - From SWPP | P - From MS4 (☑ Check All That Apply; Provide Info Where Indicated) |
| | | Aquifers present |
| e. Aquifers | | Regulatory sole source aquifer present |
| - | | No aquifers |
| f. Infiltration rate of soils | | Less than 0.5 inches/hour |
| 1. Infinitation rate of sons | | Greater than 0.5 inches/hour |
| g. Depth to seasonal high | | Less than or equal to 3 ft |
| groundwater table | | Greater than 3 ft |
| i Donth to hadroals | | Less than or equal to 2 ft |
| i. Depth to bedrock | | Greater than 2 ft |
| 11. Stormwater hotspots | | Proposed project includes one or more of activities, listed below. Check all that apply |
| | | *vehicle salvage yards and recycling facilities; |
| - | | vehicle fueling stations |
| - | | vehicle service and maintenance facilities; |
| List of stormwater hotspots | | *vehicle and equipment cleaning facilities |
| from NYSDEC Stormwater | | *fleet storage areas (bus, truck, etc.) |
| Management Design Manual (2015) Chapter 4. Those asterisked need a stormwater | | industrial sites (based on SIC codes outlined in the SPDES General Permit for Stormwater Discharges Associated with Industrial Discharges) |
| pollution prevention plan. | | *marinas (service and maintenance) |
| "Hotspot" projects have additional post construction | | outdoor liquid container storage; |
| stormwater practices design | | outdoor loading/unloading facilities |
| requirements. | | public works storage areas; |
| | | *facilities that generate or store hazardous materials; |
| | | commercial container nursery |
| | | none of the above |

| CONTENT | | | | | | | | | | |
|---|---|---------|--|--|--|--|--|--|--|--|
| Part II. | SWPPP Content Check List - Long Version | Part II | | | | | | | | |
| A. Project Parameters | Project location; site regulatory features; local laws; policy documents; physical geography; eligibility for construction activity permit coverage; project type (E/SC only, E/SC-Post Cons) | p.2 | | | | | | | | |
| B. Forms and Documents | Forms and documentation to submit with SWPPP | p.6 | | | | | | | | |
| C. Erosion and Sediment Control Components | Required SWPPP content named in Construction Activity Permit GP-0-15-002 and by request from MS4s | p.10 | | | | | | | | |
| D. Post Construction Stormwater Management Components | Required SWPPP content named in Construction Activity Permit GP-0-15-002; the NYS Stormwater Management Design Manual (2015); and by request from MS4s | p.17 | | | | | | | | |
| E. Municipal Requirements-Maps, Construction Drawings, Standards | Requirements developed by MS4s to help standardize SWPPP submissions, clarify MS4 expectations, and visualize all phases of the construction project | p.31 | | | | | | | | |

Part II. SWPPP Content Check List-Long Version A. Project Parameters

Project:_____ Date:_____

| | | | nt Check L | | | | | |
|----------|---------------|-------------|------------------|-----------------|----------------|--------------------|-----------|--|
| A. Proje | ect Parar | neters (| (location; p | roject activ | vities; s | ite geograph | ıy; regul | atory features; eligibility for permit coverage; E-SC Only or E-SC & Post C.) |
| | SW | PPP Pr | eparer | S | WPPP | Reviewer(s) | | Project Information |
| Item | Ø, if present | ⊠, if NA | Item Location | Consul ☑, if | ltant ☑, if | MS4 Staff ☑, if | ØOthers | SWPPP Contents |
| | present | 1121 | (Pg #) | present | NA | present | NA | |
| 1 | | | | | | | | 1. General Information |
| 2 | | | | | | | | a. Project name |
| 3 | | | | | | | | b. Project location (which municipality) |
| 4 | | | | | | | | c. Project location (tax map numbers-Section/Block/Lot) |
| 5 | | | | | | | | d. Project location (latitude and longitude; centroid of project; NYTM Units, UTM coordinates). Source of geographic information (NYSDEC Stormwater Interactive Map; NYSDEC Environmental Mapper; Other) |
| 6 | | | | | | | | e. Project address (if available) |
| 7 | | | | | | | | f. Name of project owner or operator |
| 8 | | | | | | | | g. Address of project owner or operator |
| - | | | | | | | | h. If SWPPP MS4 Acceptance Form required, name of |
| 9 | | | | | | | | MS4/municipality signing form. |
| 10 | | | | | | | | 2. Project Specifics |
| 11 | | | | | | | | a. General overview (purpose and extent of proposed development). |
| 12 | | | | | | | | b. Project area (acres): total site area; total disturbed area; total undisturbed area. Clear statement that total disturbed includes the entire |
| 12 | | | | | | | | common plan of development. |
| 13 | | | | | | | | d. Description of project type (erosion and sediment control only or erosion and sediment control and post construction stormwater management practices). The description explains why this project type and references appropriate activities listed in table 1 or Table 2 of Appendix B of the GP-0-15-002 Construction Activity Permit. All relevant activities are included in the description. |
| 14 | | | | | | | | e. If project is a single family home or single family residential subdivision, project type is stated clearly given percentage of impervious cover at site build-out and location of project relative to potential discharges into 303(d) impaired segements named in the Construction Activity Permit (Appendix E) and MS4 Permit (Appendix 2). |
| 15 | | | | | | | | f. If project requires post construction stormwater management practices desciption states whether or not it is New Development, New Development in an Enhanced Phosphorus Removal Watershed, Redevelopment Activity, or Redevelopment Activity and New Development. |
| 16 | | | | | | | | g. If the project is a Redevelopment Activity, desciption notes status of impervious area (will decrease, increase, or stay the same) |
| 17 | | | | | | | | h. If project requires review and acceptance by an MS4 town, village, or city the SWPPP states the local law by number and date which authorizes oversight of construction activity by the MS4; describes the land disturbance acreage which triggers submission of SWPPP; and names local municipal permits for clearing, grubbing, grading, or excavating required by the municipality before land disturbance can begin. Permits may/may not be named in local law. |

Part II. SWPPP Content Check List-Long Version A. Project Parameters

Project:____ Date:_____

| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | Project Information |
|------|---------------|-------------|--------------------|---------------|-------------|------------------|-------------|---|
| Item | ۲. f | | Item | Consultant | | MS4 Staff/Others | | |
| | Ø, if present | ⊠, if NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | SWPPP Contents |
| 18 | | | | | | | | i. If project is located in a municipality which owns and operates both a separated storm sewer system and a combined sanitary/stormwater system the SWPPP describes which infrastructure will receive stormwater runoff from this project and describes which local laws, design criteria, and/or regulatory requirements will guide project design |
| 19 | | | | | | | | j. If project is owned by the MS4, the SWPPP references operating procedures used to guide oversight of construction activity and describe any policy documents used to guide the design of post construction stormwater practices. |
| 20 | | | | | | | | k. If the project requires post construction practices, the SWPPP list all of the practices proposed for this site by name from the NYSDEC Stormwater Management Design Manual (2015) as well as proprietary practices. Practices not designed in conformance with the performance criteria of the Design Manual are noted. |
| 21 | | | | | | | | 3. Physical Geography; Regulatory Features; Eligibility for General Permit Coverage |
| 22 | | | | | | | | a. Name of all waterbodies receiving stormwater discharges from this site (includes initial stream segment(s) by NHD stream ID number if possible; stream order of the initial segment(s); identification of segment as tributary, if appropriate; and name of the final receiving water). |
| 23 | | | | | | | | b. Stream classification of initial receiving waters of construction activity discharges. Note if receiving waters are trout streams (Class C (T) or Class C (TS)) or tributary to source of drinking water (Class AA or AA-s; and b). |
| 24 | | | | | | | | c. Regulatory status of initial receiving water of construction activity discharges noting if segment is on the most current NYSDEC 303(d) impaired waterbody list; listed in Appendix E of GP-0-15-002 Construction Activity Permit; listed in Appendix 2 of GP-0-15-003 MS4 Permit (primary pollutant of concern. named) |
| 25 | | | | | | | | For Albany County: |
| 26 | | | | | | | | Construction Activity Permit Appendix E 303(d) impaired waterbodies are Ann Lee (Shakers) Pond,/Stump Pond and Basic Creek Reservoir |
| 27 | | | | | | | | MS4 Permit Appendix 2 impaired waterbodies are Ann Lee (Shakers) Pond/Stump Pond, primary pollutant of concern phosphorus and Basic Creek Reservoir, primary pollutant of concern phosphorus. |
| 28 | | | | | | | | d. Description of separated storm sewer systems which receive discharges from this project (Who owns it? If MS4, name of MS4.) |
| 29 | | | | | | | | e. Description, if any of land areas where there is no existing imperviou cover and where discharges from construction activities are undertaken on land with a Soil Slope Phase that is identified as an E or F, or the map unit is inclusive of 25% of greater slope on the United State Department of Agriculture ("USDA") Soil Survey for the County. |

Part II. SWPPP Content Check List-Long Version A. Project Parameters

| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | Project Information |
|------|---------------|-------------|----------------------------|---------------|-------------|------------------|-------------|--|
| Item | | | Item Location (Pg #) | Consu | ltant | MS4 Staff/Others | | |
| | ☑, if present | ⊠, if NA | | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | SWPPP Contents |
| 30 | | | | | | | | f. Description, if any of construction activities or discharges that may adversely affect an endangered or threatened species and actions taken address issue. (See Check List Part IV. SWPPP Contents A. Documents). |
| 31 | | | | | | | | g. Description, if any of construction activities that have the potential to affect an historic property and actions taken to address the issue. (See GP-0-15-002 Construction Activity Permit Part I.F.8 and Check List Part IV. SWPPP Contents A. Documents) |
| 32 | | | | | | | | h. Description of natural features influencing construction and maintenance of erosion and sediment controls (site slopes; soil erobility/K-value; infiltration rate; type of soils) |
| 33 | | | | | | | | i. Description of natural features influencing design of post constructio practices(site slopes; soil erobility/K-value; presence/absence of karst topography; depth to seasonally high water table; depth to bedrock; presence/absence of aquifers, including sole source aquifers; site hydrological soil groups ("HSG"); infiltration rate) |
| 34 | | | | | | | | j. Description of man-made features influencing design of post construction practices (presence/absence of fill, utility lines; brownfields; underground storage tanks) |
| 35 | | | | | | | | k. Description, if any of stormwater hotspots associated with the intended land use or activity of project. Description notes those activiti required to prepare a stormwater pollution prevention plan are identifie |
| 36 | | | | | | | | Land uses and activities deemed stormwater hotspots are listed in the NYS Storomwater Manageement Design Manual (2015) Chapter 4 as follows, with those asterisked needing a stormwater pollution prevention plan: *vehicle salvage yards and recycling facilities; vehicle fueling stations; vehicle service and maintenance facilities; *vehicle and equipment cleaning facilities; *fleet storage areas (bus, truck, etc.); industrial sites (based on SIC codes outlined in the SPDES General Permit for Stormwater Discharges Associated with Industrial Discharges Multi-Sector General Permit; *marinas (service and maintenance); outdoor liquid container storage; outdoor loading/unloading facilities; public works storage areas; *facilities that generate or store hazardous materials; commercial container nursery; other land uses as designated by an appropriate authority. |
| 37 | | | | | | | | 4. General Permit Coverage for Construction Activity |
| 38 | | | | | | | | a. Statement affirming that this land disturbance project is eligible for general permit coverage under NYSDEC SPDES GP-0-15-002 Construction Activity Permit. |
| 39 | | | | | | | | If this project results in discharges or activities as described below and the necessary permits are not obtained, the project can not be authorized for Construction Activity general permit coverage. (See NYSDEC GP-0-15-003 Construction Activity Permit Part I.E, pgs.10- 12) |

Part II. SWPPP Content Check List-Long Version A. Project Parameters

| A. Proj | ect Parar | neters (| (location; p | roject activ | vities; si | ite geograph | iy; regulat | ory features; eligibility for permit coverage; E-SC Only or E-SC & Post |
|---------|-----------|----------|------------------|---------------|-------------|------------------|-------------|---|
| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | Project Information |
| Item | ⊠, if | ⊠, if | Item Location | Consultant | | MS4 Staff/Others | | SWPPP Contents |
| | present | NA | (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Swill Conclus |
| 41 | | | | | | | | ~Discharges that are mixed with sources of non-stormwater other than those expressly authorized under sub-section E. 3. of the Part and identified in the SWPPP required by this permit; |
| 42 | | | | | | | | ~Discharges that required to obtain an individual SPDES permit of another SPDES permit pursuant to Part VII.K. of this permit; |
| 43 | | | | | | | | ~Construction activites or discharges from construction activities that ma adversely affect an endangered or threatened species unless the owner or operator has obtained a permit issued pursuant to 6 NYCRR Part 182 for the project or the Department has issued a letter of non-jurisdiction for th project. All documentation necessary to demonstrate eligibility shall be maintained on site in accordance with Part II.C.2 of this permit. |
| 44 | | | | | | | | ~Discharges which either cause or contribute to a violation of water quality standards adopted pursuant to the ECL and its accompanying regulations; |
| 45 | | | | | | | | ~Construction activities for residential, commercial, and institutional projects: a. Where the discharges from the construction activities are tributary to waters of the state classified as AA or AA-s; and b. Which disturb one or more acres of land with no existing impervious cover; and Which are undertaken on land with a Soil Slope Phase that is identified as an E or F, or the map unit name is inclusive of 25% of greater slope, on th United States Department of Agriculture ("USDA") Soil Survey for the County where the disturbance will occur. |
| 46 | | | | | | | | ~Construction activities for linear transportation projects and linear utility projects: a. Where the discharges from construction activities are tributant to waters of the state classsified as AA or AA-s; and b. Which disturb two or more acres of land with no existing impervious cover; and c. Which are undertaken on land with a Soil Slope Phase that is identified as an E or F, or the map unit name is inclusive of 25% of greater slope, on the United States Department of Agriculture ("USDA") Soil Survey for the County where the disturbance will occur. |
| 47 | | | | | | | | ~Construction activities that have the potential to affect an historic property, unless there is documentation that such impacts have been resolved. The documentation necessary to demonstrate eligibility with this requirement shall be maintained on site in accordance with Part II.C.2 of this permit and made available to the Department in accordance with Par VII.F of this permit. |
| 48 | | | | | | | | ~Discharges from construction activities that are subject to an existing SPDES individual or general permit where a SPDES permit for construction activity has been terminated or denied; or where the owner o operator has failed to renew an expired individual permit. |

| | | | t Check L ts to Subn | | | | | |
|------|---------|--------|----------------------------|---------------|-------------|------------------|-------------|---|
| | SW | PPP Pr | eparer | S | WPPP | Reviewer(s) | | SWPPP Related Documents |
| Item | ⊠, if | ⊠, if | Item Location (Pg #) | Consultant | | MS4 Staff/Others | | |
| | present | NA | | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Description |
| 49 | | | | | | | | 1. Construction Activity Permit Forms |
| 50 | | | | | | | | <i>a. Notice of Intent (NOI) Form</i> for GP-0-15-002 Construction Activity Permit (filled in & signed by signatories named in the Construction Activity Permit) |
| 51 | | | | | | | | b. Notice of Intent (eNOI) Submission Form. (filled in and signed, if electronic submission is intended). |
| 52 | | | | | | | | <i>c. SWPPP Preparer Certification Form</i> for GP-0-15-002 Construction Activity Permit (filled in & signed) |
| 53 | | | | | | | | <i>d. Owner/Operator Certification Form</i> for GP-0-15-002 Construction Activity Permit (filled in & signed) |
| 54 | | | | | | | | <i>e. Contractor and Sub Contractor Certification Form</i> (filled in as much as possible.) This is an in-house form developed by the Stormwater Coalition based on language and requirements detailed in GP-0-15-002 Construction Activity Permit, Part III.A.6. At the time of SWPPP submission the content is filled in as much as possible. Prior to construction, all information must be filled in and is typically finalized at a pre-construction meeting which includes contractors and/or sub-contractors. |
| 55 | | | | | | | | <i>f. Notice of Termination (NOT) Form</i> For Construction Activities Seeking Authorization Under SPDES General Permit (filled in as much as possible, not signed). |
| 56 | | | | | | | | 2. MS4 Permit Forms Related to Oversight of Construction Activity Permit (Includes forms required by the MS4 Permit and Construction Activity Permit and other forms either developed or requested by the MS4 to help manage construction activity components of their stormwater program). |
| 57 | | | | | | | | <i>a. MS4 SWPPP Acceptance Form</i> for Construction Activities Seeking Authorization Under SPDES General Permit (filled in and not signed). Once the SWPPP is deemed acceptable by the MS4, this form is signed by the MS4 Official (principal executive officer or ranking elected officials or Duly Authorized Representative) |
| 58 | | | | | | | | b. Notice of Termination (NOT) Form For Construction Activities Seeking Authorization Under SPDES General Permit (At time of SWPPF submission, filled in as much as possible). Once project is completed, the MS4 Official must sign the Notice of Termination. |
| 59 | | | | | | | | <i>c. MS4 Construction Site Inspection Form</i> (not filled in) This is an inhouse form developed by the Stormwater Coalition or individual MS4s which is based on language and requirements detailed in GP-0-15-003 MS4 Permit Part VII.A.4.a.ix. At the time of SWPPP submission it is blank. It is included as part of the SWPPP submission for instructional purposes, highlighting for owner or operators seeking Construction Activity Permit coverage what land use control MS4s will be looking for when conducting site inspections. These inspections are mandated in the MS4 Permit. |

Part II. SWPPP Content Check List-Long Version B. Forms and Documents

Project:_____ Date:_____

| | | | nt Check L ats to Subn | | | n | | |
|------|---------|-------------|---------------------------|---------------|-------------|---------------|-------------|---|
| | SW | PPP Pro | eparer | S | WPPP I | Reviewer(s) | | SWPPP Related Documents |
| Item | ⊠, if | ⊠, if | Item | Consul | tant | MS4 Staff/ | /Others | |
| | present | ≥, II NA | Location (Pg #) | ⊠, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Description |
| 60 | | | | | | | | <i>d. Blank copy of owner or operator: Contractor Maintenance</i> <i>Inspection Report Form</i> (This form is used by the trained contractor to inspect erosion and control practices and pollution prevention measures being implemented within the active work area daily to ensure that they are being maintained in effective operation at all times. The form may be part of the Qualified Inspector Form. It could also be the form used for single family construction projects not required to have a qualified inspector. |
| 61 | | | | | | | | <i>e. Blank copy of owner or operator: "Qualified Inspector" Inspection</i> <i>Report Form</i> , (Items to include in the form are listed in the Construction Activity Permit, Part IV.C.2.4. pg. 27-28. This form is used for site inspections of all construction activites, with the exception of: the construction of a single family residential subdivision with 25% less impervious cover at total build-out that involves a soil disturbance of one (1) or more acres of land but less than five (5) acres of land and is not located in Appendix C watersheds (East of Hudson; Onondaga Lake; Greenwood Lake; Oscawana Lake; Kinderhook Lake) and <u>not</u> directly discharging to one of the 303(d) segment listed in Appendix E |
| 62 | | | | | | | | 3. Other Documents Named in Construction Activity Permit (GP-0-15-002) |
| 63 | | | | | | | | a. State Historic Preservation Act (SHPA) |
| 64 | | | | | | | | Documentation of Eligibility for General Permit Coverage State Historic Preservation Act (SHPA) requirements. As described in Part I.F.8.a to d. of Construction Activity Permit GP-0-15-002, determining "SHPA"- related eligibility involves multiple steps. As of the release of this check list, required regulatory paperwork is incomplete, in particular the Construction Activity Permit NOI has yet to include questions referenced in the Cultural Resource and Potential Cultural Impacts Flow Charts (Questions 14, 15, 16, and 17). However some SHPA related documentation can be submitted with the SWPPP, as follows. |
| 65 | | | | | | | | <i>Cultural Resources Screening Flow Chart.</i> Use Flow Chart to explain if the project is Eligible or Not Eligible for coverage, state why. For Eligible Projects note which documents need to be maintained on site. |
| 66 | | | | | | | | For Eligible Projects, include with the SWPPP submission, documents to be maintained on site. Possible documents are listed below: |
| 67 | | | | | | | | Map showing that the project is not within an archeological sensitive area and not located or immediately adjacent to a property listed or determined to be eligible for listing on the National and State Register o Historic Places |
| 68 | | | | | | | | ii. Documentation showing the age of all buildings, structures or objects within the specified distances are less than 50 years old. (If 2015, 50 years = 1965) |
| 69 | | | | | | | | iii. Documentation from OPRHP, a Historic Preservation Commission of a Certified Local Government, or a qualified preservation professional stating the buildings, structures, or objects that are more than 50 years old within the specified distances are not historically/archeologically significant. |

| | | | nt Check L nts to Subn | | | n | | |
|----------|---------|--------|---------------------------|---------------|-------------|---------------|-------------|---|
| | | PPP Pr | | | | Reviewer(s) | | SWPPP Related Documents |
| Item | ⊠, if | ⊠, if | Item | Consul | tant | MS4 Staff | /Others | |
| | present | MA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Description |
| 70 | | | | | | | | For Not Eligible Projects, review Resolution of Potential Cultural Impacts Flow Chart; submit a Request for State Historic Preservation Act Review; summarize determination. Include the original Request for State Historic Preservation Review and related documentation with SWPPP submission. |
| 71 | | | | | | | | Following a State Historic Preservation Review, for projects eventually determined to be eligible by OPRHP and DEC, note what documents need to be maintained on site and include with SWPPP submission. Possible docuements are listed below; note which are applicable/not applicable. |
| 72 | | | | | | | | i. NHPA 106 Documents: No Adverse Impact, No Affect, or Memorandum of Agreement |
| 73 | | | | | | | | ii. SHPA 14.09 documents |
| 74 | | | | | | | | iii. SEQR EAF with Negative Declaration or Findings Statement; Documentation of OPRHP's agreements with resolution; DEC consultation form sent to OPRHP and copy to DEC APO (Agency Preservation Officer?) |
| 75 | | | | | | | | iv. Letter of No Impact and DEC Consultation Form |
| 76 | | | | | | | | v. Letter of No Adverse Impact and DEC Consultation Form |
| 77 | | | | | | | | vi. Letter of Resolution (LOR) and DEC Consultation Form |
| 78 | | | | | | | | For Projects which continue to be Not Eligible for coverage, continue to work with DEC APO and OPRHP to resolve. If SHPA issues can not be resolved, the project is ineligible for permit coverage under the general permit for Construction Activity. Other options need to be discussed with NYSDEC. |
| 79 | | | | | | | | b. State Environmental Quality Review Act ("SEQRA") |
| 80 | | | | | | | | Documentation that project review pursuant to the <i>State Environmental</i> <i>Quality Review Act ("SEQRA")</i> has been satisfied, when SEQRA is applicable. |
| 81 | | | | | | | | c. Uniform Procedures Act ("UPA") |
| 82 | | | | | | | | Documentation that where required, that all necessary Department permits subject to the Uniform Procedures Act ("UPA") (see 6 NYCRR Part 621 of NYS Environmental Conservation Law (ECL), Article 70) have been obtained. |
| 83 | | | | | | | | Below is a list of permits included in the GP-0-15-002 Construction Activity Permit Notice Of Intent (pg. 13), presumably named in the "Uniform Procedures Act". For this Check List, note which Permits are "not applicable"; for those permits which are applicable, include with the SWPPP submission. |
| 84 | | | | | | | | Air Pollution |
| 85 | | | | | | | | Coastal Erosion |
| 86 | | | | | | | | Hazardous Waste |
| 87 | | | | | | | | Long Island Wells |
| 88 | | | | | | | | Mined Land Reclamation |
| 89 | | | | | | | | Solid Waste |
| 90 | | | | | | | | Navigable Waters Protection/Article15 |
| 91 92 | | | | | | | | Water Quality Certification Dam Safety |
| 92 | | | <u> </u> | | | | | Water Supply |
| 93 | | | | | | | | Freshwater Wetlands/Article 24 |
| 95 | | | | | | | | Tidal Wetlands |

Part II. SWPPP Content Check List-Long Version B. Forms and Documents

| | | | nt Check L nts to Subr | | | | | | |
|------|---------------|-------------|---------------------------|---------------|---|---------------|-------------|--|--|
| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | SWPPP Related Documents | |
| Item | | | Item | Consu | ltant | MS4 Staff | /Others | | |
| | ☑, if present | ⊠, if NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Description | |
| 96 | | | | | | | | Wild, Scenic, and Recreational Rivers | |
| 97 | | | | | | | | Stream Bed or Bank Protection/Article 15 | |
| 98 | | | | | | | | Endangered or Threatened Species (Incidental Take Permit) | |
| 99 | | | | | | | | Individual SPDES Permit | |
| 100 | | | | | | | | SPDES Multi-Sector Permit | |
| 101 | | | | | | | | Other | |
| 102 | | | | | | | | d. Federal Permits | |
| 103 | | | | | | | | i. Underground Injection Control Permit | |
| 104 | | | | | | | | Copy of permit when certain conditions are met (see NYSDEC Stormwater Management Design Manual (2015), Chapter 4, Section 4.3, page 4-7 for details and reference to EPA documents). | |
| 105 | | | | | | | | ii. Army Corps of Engineers-Wetland Permits | |
| 106 | | | | | 4. Documents Pertaining to Post Construction Stormwater Management Practices (Required by MS4) | | | | |
| 107 | | | | | | | | All necessary stormwater easement documentation, if applicable. | |
| 108 | | | | | Maintenance Agreement | | | | |

| | | | nt Check L nt Control | | | n | | | |
|------------|---------|--------|--------------------------|---------------|-------------|---------------|-------------|--|---|
| | | PPP Pr | | | | Reviewer(s) | | Erosion and Sediment Cor | ntrol Components |
| Item | ⊠, if | ⊠, if | Item | Consul | tant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| | present | NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 | MS4 Clarificatons & Requests |
| 109 | | | | | | | | Erosion and sediment control component - All SWPPPs prepared pursuant to this permit shall include erosion and sediment control practices designed in conformance with the technical standards, New York State Standards and Specifications for Erosion and Sediment Control, dated August 2005. Where erosion and sediment control practices are not designed in conformance with the design criteria included in the technical standard, the owner or operator must demonstrate <i>equivalence</i> to the technical standard. | |
| 110 | | | | | | | | | If construction activity is a single family home, use Appendix E Erosion and Sediment Control Plan for Small Homesite Construction from the NYS Standards and Specifications for Erosion and Sediment Control dated August, 2005 or provide equivalent details and specifications. |
| 111 | | | | | | | | At a minimum, the erosion and sediment control component of the SWPPP, shall include the following: | |
| 112 | | | | | | | | Background info about: scope of project, including location, type, and size of project. | |
| 113 | | | | | | | | ~location | |
| 114 115 | | | | | | | | ~type ~size | |
| 116 | | | | | | | | Site map/construction drawing(s) for the project, including a general location map. | |
| 117 | | | | | | | | At a minimum, the site map shall show: | |
| 118 | | | | | | | | ~the total site area; | |
| 119 | | | | | | | <u> </u> | ~all improvements; | |
| 120 | | | | | | | | ~areas of disturbance; | |
| 121 | | | | | | | | ~areas that will not be disturbed; ~on-site and adjacent off-site surface | |
| 122 | | | | | | | | water(s); | |
| 123 | | | | | | | | ~floodplain/floodway boundaries; | |
| 124 | | | | | | | | ~wetlands and drainage patterns that could be affected by the <i>construction</i> <i>activity;</i> | |
| 125 | | | | | | | | ~existing and final contours; | |
| 126 | | | | | | | | | ~existing and final proposed topography a minimum of 50' beyond the property (min. 2'contours) or as required by MS4 |

| | | | nt Check L nt Control | | | n | | | |
|---------|---------|--------|--------------------------|---------------|-------------|---------------|-------------|--|--|
| C. E105 | | PPP Pr | | - | | Reviewer(s) | | Erosion and Sediment Cor | atrol Components |
| | 511 | | eparer | | | ~ / | | | - |
| Item | ⊠, if | ⊠, if | Item Location | Consul | 1 | MS4 Staff | 1 | Required SWPPP Content | Additional SWPPP Content |
| | present | NA | (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 | MS4 Clarificatons & Requests |
| 127 | | | | | | | | ~locations of different soil types with boundaries; | |
| 128 | | | | | | | | ~material waste, borrow, or equipment storage areas located on adjacent properties; | |
| 129 | | | | | | | | | Specific details for: |
| 130 | | | | | | | | | ~material stockpiling |
| 131 | | | | | | | | | ~equipment staging |
| 132 | | | | | | | | | ~material storage |
| 133 | | | | | | | | | ~borrow/spoil areas |
| 134 | | | | | | | | | ~dewatering operations |
| 135 | | | | | | | | | ~spill/waste containment |
| 136 | | | | | | | | | ~concrete wash-out |
| 137 | | | | | | | | <pre>~location(s) of stormwater discharge(s);</pre> | |
| 138 | | | | | | | | | ~boundary of the proposed limits of clearing and, if different, limits of grading on the site. |
| 139 | | | | | | | | A description of the soil(s) present at the site, including identification of the Hydrological Soil Group. | |
| 140 | | | | | | | | Construction phasing plan and sequence of operations describing the intended order of <i>construction activities</i> , including: | Phasing plan must limit active disturbance to under 5 acres. |
| 141 | | | | | | | | ~clearing and grubbing; | |
| 142 | | | | | | | | ~excavation and grading; | |
| 143 | | | | | | | | ~utility and infrastructure installation; | |
| 144 | | | | | | | | ~any other activity at the site that results in soil disturbance | |
| 145 | | | | | | | | | ~stockpiling |
| 146 | | | | | | | | | ~final stabilization |
| 147 | | | | | | | | A description of the minimum erosion and sediment control practices to be installed or implemented for each construction activity that will result in soil disturbance. Include a schedule that: | |
| 148 | | | | | | | | ~ identifies the timing of initial placement or implementation of each erosion and sediment practice and; | |
| 149 | | | | | | | | ~the minimum time frames that each practice should remain in place or be implemented. | |

| | | | nt Check L nt Control | - | | | | | | |
|------|---------|-----------|--------------------------|---------------|-------------|---------------|-------------|--|--|--|
| | SW | SWPPP Pre | | S | WPPP | Reviewer(s) | | Erosion and Sediment Control Components | | |
| Item | ⊠, if | ⊠, if | Item | Consul | tant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content | |
| | present | NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 | MS4 Clarificatons & Requests | |
| 150 | | | | | | | | A temporary and permanent soil stabilization plan that meets the requirements of this general permit and the technical standard, NYS Standards and Specifications for Erosion and Sediment Control dated August, 2005, for each stage of the project, including land clearing and grubbing to project completion and achievement of final stabilization. | | |
| 151 | | | | | | | | | Specifications for temporary and permanent seeding – note seed types and application rates | |
| 152 | | | | | | | | | Statement which reads that in areas where soil activity has temporarily or permanently ceased, the application of soil stabilization measures must be initiated by the end of the next business day and completed within fourteen (14) days from the date the current soil disturbance activity ceased. | |
| 153 | | | | | | | | | For construction sites that directly discharge to one of the 303(d) listed segments in Appendix E (Ann Lee (Shakers) Pond, Stump Pond, Basic Creek Reservoir), a statement which reads that the application of soil stabilization measures must be initiatiated by the end of the nex business day and completed within seven (7) days from the date the current soil disturbance activity ceased. | |
| 154 | | | | | | | | A site map/construction drawing(s) showing the specific location(s), size(s), and length(s) of each erosion and sediment control practice | | |
| 155 | | | | | | | | | Descriptions of structural practices used to divert flows from exposed soils, store flows, or otherwise limit runoff and the discharge of pollutants from the exposed areas of the site | |

| | | | nt Check L nt Control | | | n | | | |
|------------|---------|-------|--------------------------|---------------|-------------|---------------|---|--|---|
| | PPP Pr | | • | | Reviewer(s) | | Erosion and Sediment Control Components | | |
| Item | ⊠, if | ⊠, if | Item | Consultant | | MS4 Staff | Others | Required SWPPP Content | Additional SWPPP Content |
| | present | NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 | MS4 Clarificatons & Requests |
| 156 | | | | | | | | The dimensions, material specifications, installation details, and operation and maintenance requirements for all erosion and sediment control practices. Include the location and sizing of any temporary sediment basins and structural practices that will be used to divert flows from exposed soils | |
| 157 | | | | | | | | | Calculations for siting and sizing of any temporary sediment basins and/or traps |
| 158 | | | | | | | | | Identification of any maintenance or inspection actions that are required prior to converting practices to permanent control measures |
| 159 | | | | | | | | A maintenance inspection schedule for the contractor(s) identified in Part III.A.6 of GP 0-15-002, to ensure continuous and effective operation of the erosion and sediment control practices. The maintenance inspection schedule shall be in accordance with the requirements of the technical standard, NYS Standards and Specifications for Erosion and Sediment Control dated August, 2005. | |
| 160 | | | | | | | | A description of the pollution prevention measures that will be used to control litter, construction chemicals, and construction debris from becoming a pollutant source | |
| 161 | | | | | | | | ~control litter | |
| 162 163 | | | | | | | | ~construction chemicals ~construction debris | |
| 164 | | | | | | | | | Description of construction and waste materials expected to be utilized on-site or adjacent to site |
| 165 | | | | | | | | | Description of controls to reduce pollutants from these materials |
| 166 | | | | | | | | | Description of cleanup procedures and spill prevention and notification for each material |
| 167 | | | | | | | | A description and location of any stormwater discharges associated with industrial activity other than construction at the site, including but not limited to, stormwater discharges from asphalt plants and concrete plants located on the construction site. | |

| | | | nt Check L | | | n | | | |
|---------|---------------|-------------|--------------------|---------------|-------------|---------------|-------------|--|--|
| C. Eros | ion and S | Sedime | nt Control | Compone | ents | | | [| |
| | SW | PPP Pi | reparer | S | WPPP I | Reviewer(s) | | Erosion and Sediment Cor | trol Components |
| Item | | | Item | Consu | ltant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| | ☑, if present | ⊠, if NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 | MS4 Clarificatons & Requests |
| 168 | | | | | | | | Identification of any elements of the design that are not in conformance with the design criteria in the technical standard, NYS Standards and Specifications for Erosion and Sediment Control dated August, 2005 | |
| 169 | | | | | | | | ~include the reason for the deviation or alternative design | |
| 170 | | | | | | | | ~provide information which demonstrates that the deviation or alternative design is equivalent to the standard. | |
| 171 | | | | | | | | | If project is in a regulated MS4, description of winter month, October 15 to April 15, requirements related to E&SC (i.e. anchoring mulch material, sediment removal from basins/traps, use of winter rye seed, offset silt fence, etc.). See Winter Shutdown and Site Inspection Requirements available from MS4. |
| 172 | | | | | | | | TRACKING SPECIFIC DESIGN ELEMENTS: | |
| 173 | | | | | | | | To help track the review of E/SC practices for presence/absence, size, and length information, MS4s may want to call out practices of concern and note comments. Space is provided here for that purpose. | |
| 174 | | | | | | | | E/SC Practice #1 Description of Practice: Location present, Y/N? Size present Y/N? Length present, Y/N? Comments: | |

| | | | nt Check L | 0 | | n | | | | |
|----------|----------|--------|--------------------|---------------|-------------|---------------|-------------|--|------------------------------|--|
| C. Erosi | on and S | Sedime | nt Control | Compone | ents | | | | | |
| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | Erosion and Sediment Control Components | | |
| Item | ⊠, if | ⊠, if | Item | Consu | ltant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content | |
| | present | NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 | MS4 Clarificatons & Requests | |
| 175 | | | | | | | | E/SC Practice #2 Description of Practice: Location present, Y/N? Size present Y/N? Length present, Y/N? Comments: | | |
| 176 | | | | | | | | To help track the review of each E/SC practice for presence/absence of dimension, material specification, installlation details, and operation and maintenance requirements for erosion and control practices MS4s may want to call out specific practices of interest and make comments. Space is provided here for that purpose. | | |
| 177 | | | | | | | | E/SC Practice #1 Description of Practice Items present: Dimensions, Y/N? Installation details,Y/N? Operation and maintenance requirements, Y/N? If temporary sediment basin, location present, Y/N? Size present, Y/N? If structural practice to divert flows, location present, Y/N? Size present, Y/N? Comments: | | |
| 178 | | | | | | | | E/SC Practice #2 Description of Practice | | |

| | | | nt Check L nt Control | 0 | | n | | | |
|----------|---------------|-------------|--------------------------|---------------|-------------|------------------|-------------|--|------------------------------|
| C. Erosi | | PPP Pr | | | | Reviewer(s) | | Erosion and Sediment Cor | ntrol Components |
| Item | | | Item | Consul | ltant | MS4 Staff/Others | | Required SWPPP Content | Additional SWPPP Content |
| | ☑, if present | ⊠, if NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 | MS4 Clarificatons & Requests |
| 179 | | | | | | | | To help track design elements <u>not</u> in conformance with the design criteria in the technical standards, MS4s may want call out specific practices of interest, as follows, and make comments. Space is provided here for that purpose. | |
| 180 | | | | | | | | Non-Conforming Design Element #1 Description: Reason for deviation or alternate design present, Y/N_? Info demonstrating that deviation or alternative design is equivalent to standard present, Y/N_? Comments: | |
| 181 | | | | | | | | Non-Conforming Design Element #2 Description: Reason for deviation or alternate design present, Y/N? Info demonstrating that deviation or alternative design is equivalent to standard present, Y/N? Comments: | |

| | | | nt Check L tormwater | | | | | F | |
|------|------------------|-------------|----------------------------|---------------|-------------|---------------|-------------|---|--|
| | SW | PPP Pr | reparer | S | WPPP | Reviewer(s) | | Post Construction Stormwate | r Management |
| Tr | | | т. | Consul | ltant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ⊠, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 182 | | | | | | | | From Construction Activity Permit: | |
| 183 | | | | | | | | Post-construction stormwater management component-The owner or operator of any construction project identified in Table 2 of Appendix B as needing post-construction stormwater management practices shall prepare a SWPPP that includes practices designed in conformance with the applicable <i>sizing</i> <i>criteria</i> in Part I.C.2.a.,c. or d. of this permit and <i>performance criteria</i> in the technical standard, New York State Stormwater Management Design Manual dated January 2015. | |
| 184 | | | | | | | | Where post-construction stormwater management practices are not designed in conformance with the <i>performance criteria</i> in the technical standard, the <i>owner or</i> <i>operator</i> must include in the SWPPP the reason(s) for the deviation or alternative design and provide information which demonstrates that the deviation or alternative design is <i>equivalent</i> to the technical standard. | |
| 185 | | | | | | | | The post-construction stormwater management practice component of the SWPPP shall include the following: | |
| 186 | | | | | | | | Identification of all post-construction stormwater management practices to be constructed as part of the project. Include the dimensions, material specifications and installation details for each post-construction stormwater management practice. | |
| 187 | | | | | | | | A site map/construction drawing(s) showing the specific location and size of each post-construction stormwater management practice | |
| 188 | | | | | | | | Stormwater Modeling and Analysis Report that includes: | |
| 189 | | | | | | | | ~Map(s) showing pre-development conditions, including watershed/sub- catchment boundaries, flow paths/routing, and design points | Watershed/sub-catchment includes any upstream watersheds draining onto the project site and the associate stormwater collection and conveyance structures |

| | | | nt Check L tormwater | - | | | | | |
|--------|---------------|-------------|----------------------------|------------------|-------------|---------------|-------------|--|--|
| 1 0.51 | | PPP Pro | | | | Reviewer(s) | | Post Construction Stormwate | r Management |
| | | | - | Consul | ltant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 190 | | | | | | | | ~Map(s) showing post-development conditions, including watershed/sub- catchment boundaries, flow paths/routing, design points, and post-construction stormwater practices | Watershed/sub-catchment includes any upstream watersheds draining onto the project site and the associated stormwater collection and conveyance structures |
| 191 | | | | | | | | ~Results of stormwater modeling (i.e. hydrology and hydraulic analysis) for the required storm events, include supporting calculations (model runs), methodology, and a summary table that compares pre and post development runoff rates and volumes for different storm events. | |
| 192 | | | | | | | | ~Summary table, with supporting calculations, which demonstrates that each post- construction stormwater practice has been designed in conformance with the <i>sizing criteria</i> included in the Design Manual | |
| 193 | | | | | | | | ~Identification of any sizing criteria that is not required based on the requirements included in Part I.C. of this permit. | |
| 194 | | | | | | | | ~Identification of any elements of the design that are not in conformance with the <i>performance criteria</i> in the Design Manual. Include the reason(s) for the deviation or alternative design and provide information which demonstrates that the deviation or alternate design is <i>equivalent</i> to the Design Manual. | |
| 195 | | | | | | | | Soil testing results and locations (test pits, borings) | Logs and mapping of borehole or test pits for all identified post construction practices. Testing is conducted in conformance with the NYS Stormwater Management Design Manual (2015) Appendix D. Includes the geotechnical report, if generated. Soil tests at location of practice, to depth of practice, seasonal high groundwater elevation noted. |
| 196 | | | | | | | | Infiltration results, when required, in particular at location of stormwater management practices. | |

| | | | nt Check L | _ | | | | | |
|------------|---------------|-------------|----------------------------|---------------|-------------|---------------|-------------|---|---|
| D. Post | | | tormwater | | | _ | | | |
| | SW | PPP Pr | eparer | S | WPPP 1 | Reviewer(s) | | Post Construction Stormwate | r Management |
| | | | | Consul | ltant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 197 | | | | | | | | From Construction Activity Permit: | |
| 198 | | | | | | | | If Enhanced Phosphorus Removal Watershed(s): | |
| 199 | | | | | | | | All construction projects identified in Table 2 of Appendix B that are located in the watersheds identified in Appendix C shall prepare a SWPPP that includes post-construction stormwater management practices designed in conformance with the applicable <i>sizing criteria</i> in Part I.C.2.b.c. or d. of this permit and the performance criteria, Enhanced Phosphorus Removal Standards included in the Design Manual. | |
| 200 | | | | | | | | Chapter 3 Stormwater Management Planning Requirements (Five Step Process) | MS4 Requests & Clarifications |
| 201 | | | | | | | | Planners and designers must address this approach (<i>i.e. stormwater management</i> <i>planning</i>) in a step-wise process that involves site planning and stormwater management practice (SMP) selection. This includes providing information in the SWPPP which documents compliance with the required process. The steps include: | |
| 202 | | | | | | | | The Six Step Process for Stormwater Site Planning and Practice Selection | |
| 203 | | | | | | | | Step 1 Site Planning | |
| 204 | | | | | | | | The designer uses practices identified in Design Manual Chapter 3, Table 3.1 to protect natural resources and utilize the hydrology of the site before laying out the proposed development. The Preservation of Natural Resources practices include protecting natural areas, avoiding sensitive areas and minimizing grading and soil disturbance. | Text or chart which describes how Preservation o Natural Resources practices have been incorporated into the SWPPP Stormwater Management Plan. |
| 205 | | | | | | | | Table 3.1 Green Infrastructure Planning General Categories and Specific Practices | |
| 206 | | | | | | | | Preservation of Natural Resources Practices | |
| 207 | | | | | | | | Preservation of Undisturbed Areas | |
| 208 209 | ļ | | | | | | | Preservation of Buffers Reduction of Clearing and Grading | |

| | | | nt Check L | | | | | | |
|---------|------------------|-------------|----------------------------|---------------|-------------|---------------|-------------|--|---|
| D. Post | Construc | ction St | tormwater | Managen | nent Co | omponents | | | |
| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | Post Construction Stormwate | r Management |
| Itam | | | Itam | Consul | tant | MS4 Staff | Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 210 | | | | | | | | Locating Development in Less Sensitive Areas | |
| 211 | | | | | | | | Open Space Design | |
| 212 | | | | | | | | Soil Restoration | |
| 213 | | | | | | | | The designer then considers practices to reduce impervious cover when laying out the intial site design. The Reduction of Impervious Cover practices include conservation design and reducing impervious cover in roads, drivewayts, and parking lots | Text or chart which describes how Reduction of Impervious Cover practices have been incorporated into the SWPPP Stormwater Management Plan. |
| 214 | | | | | | | | Table 3.1 Green Infrastructure Planning General Categories and Specific Practices (cont'd). | |
| 215 | | | | | | | | Reduction of Impervious Area Practices | |
| 215 | | | | | | | | Reduction of Impervious Area Fractices Roadway Reduction | |
| 210 | | | | | | | | Sidewalk Reduction | |
| 217 | | | | | | | | Driveway Reduction | |
| 218 | | | | | | | | Cul-de-sac Reduction | |
| 219 | | | | | | | | Building Footprint Reduction | |
| 220 | | | | | | | | Parking Reduction | |
| 222 | | | | | | | | The SWPPP must include an evaluation of all green infrastructure planning measures as they apply to the site. The evaluation process requires the following measures: | |
| 223 | | | | | | | | 1. Developing a map that identifies natural resource areas and drainage patterns, including, but not limited to: | |
| 224 | | | | | | | | ~Wetlands (jurisdictional, wetland of special concern) | ~Map includes NYSDEC freshwater wetlands and adjacent area boundaries or certification of no wetlands |
| 225 | | | | | | | | | ~Map includes boundary of US Army Corps of Engineers wetlands under federal jurisdiction or certification of no wetlands |
| 226 | | | | | | | | ~Waterways (major, perennial, intermittent, springs) | ~Map includes location of adjacent perennial and intermittent streams using NYSDEC classification and naming of surface waters, note as text or on map, waterways included on the impaired 303 (d) waterbody list |

| | | | nt Check L | | | n omponents | | | |
|---------|---------------|-------------|----------------------------|---------------|-------------|----------------|-------------|--|---|
| 0.1.050 | | PPP Pre | | | | Reviewer(s) | | Post Construction Stormwate | er Management |
| | | | | Consul | tant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 227 | | | | | | | | ~Buffers (stream, wetlands, forest, etc.) | ~Map includees location and boundaries of resource areas and status of protection (protected/not protected); includes stream buffers, wetland buffers, forest buffers, etc.) |
| 228 | | | | | | | | ~Floodplains | ~Map includes100-yr floodplain and floodway limits if disturbance proposed is in the floodplain |
| 229 | | | | | | | | ~Forest, vegetative cover | ~Map includes description and boundaries of the existing predominant vegetative cover on the project site |
| 230 | | | | | | | | ~Critical areas | ~Map includes location and boundaries of resource protection areas (water supply well setbacks, septic system setbacks, sole source aquifers, etc.) |
| 231 | | | | | | | | ~Topography (contour lines, existing flow paths, steep slopes, etc.) | ~Map includes existing topography a minimum of 50' beyond the property (min. 2'contours), or as required by MS4 |
| 232 | | | | | | | | ~Soil (hydrological groups, highly erodible soils, etc.) | ~Map includes description and map of all soils on the site (HSG, highly erodible soils, E and F Soil Slope Phase, others) |
| 233 | | | | | | | | ~Bedrock, significant geological features | ~Map notes location of karst bedrock, if any |
| 234 | | | | | | | | | ~If project near Hudson River, map notes location of sea-level rise projections along Hudson for 2020, 2050, and 2080 ClimAID Supplement Risk Information September, 2014 (Rule making pending-Community Risk and Resiliency Act) |
| 235 | | | | | | | | 2. Devising the strategies for protection and enhancement of natural resources | |
| 236 | | | | | | | | Prior to site layout, preserve natural features (site fingerprinting) | |
| 237 | | | | | | | | Utilize natural features to preserve the natural hydrology | |

| | | | t Check L ormwater | - | | n omponents | | | |
|------|---------------|-------------|----------------------------|---------------|-------------|----------------|-------------|---|---|
| | | PPP Pro | | | | Reviewer(s) | | Post Construction Stormwate | r Management |
| | | | | Consul | tant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ⊠, if present | ⊠, if NA | Item Location (Pg #) | ⊠, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 238 | | | | | | | | Maximize the retention of forest cover and undisturbed soils | |
| 239 | | | | | | | | Avoid erodible soils on steep slopes and limit mass grading | |
| 240 | | | | | | | | 3. Reduce the impacts of development by reducing impervious surfaces | |
| 241 | | | | | | | | 4. Demonstrating that all reasonable opportunities for preserving natural conditions of the site are employed to minimize the runoff and maintain the pre- construction hydrology | |
| 242 | | | | | | | | During the planning step, the designer should check with municipalities to determine if there are local laws and ordinances that regulate wetlands, stream buffers, forest or habitat protection, erosion control or grading. The designer should also consult the municipalilty for laws relating to conservation or cluster design, roads, driveways, and parking lots to determine level of flexibility in reducing impervious surfaces. | SWPPP acknowledges and |
| 243 | | | | | | | | Step 2 Determine Water Quality Treatment Volume (WQv) | |
| 244 | | | | | | | | The designer calculates the required WQv for the site using criteria in Chapter 4. Once the preliminary site layout is prepared: | |
| 245 | | | | | | | | ~impervious areas are defined | SWPPP calculates impervious area using Design Manual Chapter 4 definition. Total area, impervious area, % impervious calculated for each sub-catchment. % impervious used in WQv calculations. |
| 246 | | | | | | | | ~sub-catchments are delineated | SWPPP text and related maps identify the sub-catchments used to calculate water quality volume (WQv). |
| 247 | | | | | | | | ~designer calculates the water quality volume | Water quality volume calculations matched to sub- catchment and impervious areas. |
| 248 | | | | | | | | Step 3 Apply Runoff Reduction Techniques and Standards SMPs with RRv Capacity (e.g. infiltration practices, bioretention, open channel practices) to Reduce Total WQv | |

| D. Post | Constru | ction S | tormwater | Managen | nent Co | omponents | | | |
|---------|---------------|-------------|----------------------------|---------------|-------------|---------------|-------------|--|--|
| | sw | PPP Pr | eparer | S | WPPP | Reviewer(s) | | Post Construction Stormwate | r Management |
| Itam | | | T. | Consul | ltant | MS4 Staff/ | Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 249 | | | | | | | | Designer experiments with combinations of runoff reduction techniques and standard SMPs with RRv capacity on site. In each | SWPPP includes a thorough and clear analysis of: |
| 250 | | | | | | | | case, the designer estimates the spatial area to be treated by each runoff reduction | 1) how the require total WQv was calculated; |
| 251 | | | | | | | | technique, potentially reducing the required WQv by incorporating runoff reduction techniques or standard SMPs with RRv capacity within each drainage area on the | description and calculation of minimum runoff reduction requirement; |
| 252 | | | | | | | | site. | 3) description of runoff reduction calculations for each of the techniques listed in Table 3.2 and SWPs with RRV capacity; |
| 253 | | | | | | | | | reason why a particular runoff reduction technique or techniques were selected by the designer; |
| 254 | | | | | | | | | 5) reasons why a particular runoff reduction technique was not selected; and |
| 255 | | | | | | | | | 6) for redevelopment project use of any runoff reduction techniques, if any |
| 256 | | | | | | | | Table 3.2 Runoff Reduction Techniques: | |
| 257 | | | | | | | | Conservation of Natural Areas | |
| 258 | | | | | | | | Sheetflow to riparian buffers or filter strips | |
| 259 | | | | | | | | Vegetative open swale | |
| 260 | | | | | l | | | Tree planting/tree box | |
| 261 | | | | | | | | Stream daylighting for redevelopment projects | |
| 262 | <u> </u> | | | | | | | Rain garden | |
| 263 | | | | | 1 | | | Green roof | |
| 264 | | | | | | | | Stormwater planter | |
| 265 | | | | | l | | | Rain tank/cistern | |
| 266 | | | | | | | | Porous pavement | |
| 267 | | | | | | | | SMPs with RRv capacity (% of WQv provided by the practice): | |
| 268 | | | | | 1 | | | Infiltration Practices, 100% | |
| 269 | | | | | | | | Bioretention Practice, 100% in HSG A and B (without underdrain) and 40% HSG and D | |
| 270 | | | | | | | | (with underdrain) Dry Swale (Open Channel Practices), 40% in HSG A and B and 20% in HSG C and D | |

| | | | nt Check L | | | on omponents | | | |
|---------|---------------|-------------|----------------------------|---------------|-------------|-----------------|-------------|---|--|
| D. FOSU | | PPP Pr | | | | Reviewer(s) | | Post Construction Stormwate | r Management |
| | | | - | Consul | ltant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 271 | | | | | | | | If the standard SMPs with RRv capacity listed above are used to address RRv criteria, the practices must be designed to capture runoff at the source. | SWPPP text describes location of any standard SMPs with RRv capacity included in the SWPPP and provides an estimated distance from source of runoff to SMP. |
| 272 | | | | | | | | By applying a combination of runoff reduction techniques and standard SMPs with RRv capacity, the designer must reduce 100% of the WQv calculated in Step 2. If the RRv calculated in Step 3 is greater than or equal to WQv, the designer has met the RRv requirement and may proceed to Step 6. | |
| 273 | | | | | | | | Acceptable site limitations include conditions that prevent the use of an infiltration technique and or infiltration of the total WQv. Typical site limitations include: seasonal high groundwater; shallow depth to bedrock; soils with an infiltration rate less than 0.5 inches/hour. For construction activities that can not reduce the total WQv, the designer shall identify the specific site limitations in the SWPPP. | If runoff reduction volume can not be met, SWPPP states clearly specific site limitations related to all possible runoff reduction techniques. Explanation references data from soil borings, test pits, and infiltration tests. |
| 274 | | | | | | | | In the event that a designer cannot reduce 100% of the WQv due to site limitations, they shall direct runoff from all newly constructed impervious areas to a RR technique or standard SMP with RRv capacity unless infeasible. | If designer can not reduce 100% of the WQv due to site limitations, the SWPPP states which runoff reduction techniques or standard SMP with RRv capacity will be used unless infeasible. |
| 275 | | | | | | | | Step 4 Determine the minimum RRv required | |
| 276 | | | | | | | | In Step 4, the designer determines the minimum RRv required for the construction activity as calculated using the criteria in Secton 4.3 of the Design Manual and compares this to the runoff reduction achieved from impervious surfaces (determined in Step 3). In no case shall the runoff reduction achieved from the newly constructed impervious areas be less than the Minimum RRv. | SWPPP text describes how the minimum RRv was calculated. |
| 277 | | | | | | | | Step 5 Apply Standard Stormwater Management Practices to Address Remaining Water Quality Volume | |

| | | | nt Check L tormwater | | | | | | |
|------|---------------|-------------|----------------------------|---------------|-------------|------------------|-------------|--|---|
| | | PPP Pr | | | | Reviewer(s) | | Post Construction Stormwate | er Management |
| | | | | Consul | ltant | MS4 Staff/ | Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ⊠, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 278 | | | | | | | | In Step 5, the designer uses standard SMPs such as filtering practices, ponds, or stormwater wetlands to treat the remaining water quality volume that cannot be reduced by applying the runoff reduction techniques and standard SMPs with RRv capacity. The designer must verify that the RRv requirement has been met; otherwise the plan does not comply with the required sizing criteria in Chapter 4. | SWPPP text describes how much of the water quality volume will be treated using runoff reduction techniques or SMPs with RRv capacity and describes which standard SMPs will be used to treat the remaining WQv |
| 279 | | | | | | | | Step 6 Apply Volume and Peak Rate Control Practices if Still Needed to Meet Requirements | |
| 280 | | | | | | | | The channel protection volume, overbank flood control, and extreme flood control must be met for the plan to be completed. In Step 6, the designer may use practices such as infiltration basins, dry detention basins, and blue roofs to meet water quantity requirements. | SWPPP text describes which channel protection; overbank flood control, and extreme flood controls will be used to meet water quantity requirements, as needed. |
| 281 | | | | | | | | Criteria for Practice Addition | |
| 282 | | _ | | | | | | All proposed alternative stormwater management practices in new construction are considered to be in deviation from State Standards. | SWPPP text, as needed describes alternate stormwater management practices in new construction. Description includes all relevant explanations regarding equivalency, required performance and sizing criteria, and requirements related to proprietory practices. |
| 283 | | | | | | | | If alternative stormwater practices are included in SWPPP, such practices must provide a full description to justify the reasons(s) for deviation as well as detailed justification on how the proposed practice is equivalent to the standards defined n this Design Manual. | |
| 284 | | | | | | | | In order to be in compliance with the technical standards, projects must meet both the required performance and sizing criteria. | |

| | | | nt Check L tormwater | - | | | | | |
|------|---------------|-------------|----------------------------|---------------|-------------|---------------|-------------|--|--|
| | | PPP Pr | | - | | Reviewer(s) | | Post Construction Stormwate | r Management |
| | | | | Consu | ltant | MS4 Staff/ | Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ⊠, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 285 | | | | | | | | The equivalency of the performance of the proposed new technologies to the performance criteria required by New York State must be verified and certified by one of the sources accepted by the Department and documented in the SWPPP. | |
| 286 | | | | | | | | Exceptions to Meeting the Runoff | |
| 287 | | | | | | | | Reduction Volume (RRV) Criteria: 1. If a redevelopment activity, although encouraged, meeting the RRv criteria is not required for redevelopment activities that meet the criteria in Chapter 9 of the Design Manual. | If project is a redevelopment activity, SWPPP text explains Chapter 9 criteria and status of this project for meeting RRv criteria. |
| 288 | | | | | | | | 2. If karst geology, meeting the RRv criteria is required for projects over karst geology. However, use of large infiltration basins must be avoided and geotechnical assessment is recommended for infiltration and recharge at small scales | If project is located in area with karst geology, SWPPP text explains results of recommended geotechnical assessment, the need to avoid large infiltration basins; and explains why and which runoff reduction techniques are included in the SWPPP. |
| 289 | | | | | | | | 3. If the project meets the "hotspot" criteria in Chapter 4 of the Design Manual, designers shall use non-infiltration type practices to meet RRv criteria. | If project activity will result in or include any of the NYSDEC stormwater hotspots, the SWPPP describes which non- infiltration type practices will be used to meet the RRv criteria. |
| 290 | | | | | | | | Chapter 9 Redevelopment Activity NYSDEC Stormwater Management Design Manual-2015 | MS4 Requests & Clarifications |
| 291 | | | | | | | | Determinations regarding waiver of water quantity requirements: | |
| 292 | | | | | | | | 10- and 100-year water quantity control criteria waived because no change in hydrology will occur that would increase the discharge rate from the site | Calculations indicating no alteration of hydrology that would increase discharge rate (ref. Results of stormwater modeling, Ck List Item No) |

| D. Post | SWPPP Construe | ction St | tormwater | Managen | nent Co | omponents | | | |
|---------|-------------------|-------------|----------------------------|---------------|-------------|---------------|-------------|--|---|
| | SW | PPP Pr | eparer | S | WPPP | Reviewer(s) | | Post Construction Stormwate | r Management |
| | | | | Consul | tant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ⊠, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 293 | | | | | | | | Channel protection water quantity control criteria waived because no change in hydrology will occur that would increase the discharge rate from the site | Calculations showing that the post-construction 1-yr 24- hour discharge rate and velocity will not exceed the pre-construction condition (ref. Results of Stormwater Modeling: Ck List Item No. |
| 294 | | | | | | | | Treatment is required for 100% of runoff from newly created impervious surfaces and 25% of redeveloped (pre-existing) impervious surfaces | Calculation of the water quality volume with separate components for new impervious surfaces and reconstructed impervious surfaces (ref. Step 2, Determine Water Quality Treatment Volume: Ck List Item No) |
| 295 | | | | | | | | Option selected for meeting the water quality criteria for redeveloped portions of site (or all of site if no increase in impervious): | |
| 296 | | | | | | | | Impervious cover at close of construction reduced by at least 25% of the total disturbed impervious area, with soil restoration in newly created pervious areas | Site plans clearly indicate areas converted from impervious to pervious conditions and text/narrative shows acreages or square footage reduced |
| 297 | | | | | | | | A minimum of 25% of the WQv from the disturbed impervious area is captured and treated by standard practices or reduced by runoff reduction techniques. | Site plans show location of standard or runoff reduction practices and indicate the contributing drainage areas to them. |
| 298 | | | | | | | | Alternative ("proprietary") practices will treat 75% of the WQv from the disturbed impervious area as well as any additional runoff from tributary areas outside the disturbed impervious area. | Site plans show location of proprietary practices and drainage areas to them, and list the manufacturer and model for validation that the technology is accepted by NYSDEC. |
| 299 | | | | | | | | A combination of the above three approaches is proposed and weighted using the following formula: %WQv treatment by Altnerative practice = (25 - (%IC reduction + WQv treatment by Standard practice + % Runoff reduction)) x 3 | If this formula is used to determine the proportion of the WQv that must be handled by alternative practice, inputs to the calculation should be provided with supporting data. |

| | | | nt Check L | - | | | | | |
|---------|---------------|--------------------|----------------------------|---------------|-------------|---------------|-------------|--|----------------------------------|
| D. Post | | etion St PPP Pr | tormwater eparer | | | Reviewer(s) | | Post Construction Stormwate | r Management |
| | 5 | | | Consul | | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | Ø, if present | ⊠, if NA | Ø, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 300 | | | | | | | | From Construction Activity Permit: | |
| 301 | | | | | | | | An operations and maintenance plan that includes inspection and maintenance schedules and actions to ensure continuous and effective operation of each post- construction stormwater management practice. | |
| 302 | | | | | | | | Chapter 3 Stormwater Management Planning (Operations & Maintenance Plan) | |
| 303 | | | | | | | | Operations and maintenance plan, which: | |
| 304 | | | | | | | | a. identifies the location of stormwater management practice signage (runoff reduction practices and standard stormwater management practices) which notes that the sign is to be erected or posted in the immediate vicinity of the stormwater management practice, not less than 18 inches by 24 inches (or 10" x 12" for footprints smaller than 400 sf) bearing the following information: Stormwater Management Practice - (name of the practice); Must Be Maintained In Accordance With O & M Plan; DO NOT REMOVE OR ALTER | |
| 305 | | | | | | | | b. identifies entity that will be reponsible for long term operation and maintenance of each practice | |
| 306 | | | | | | | | c. identifies mechanism used to ensure long term operation and maintenance of the stormwater management practices (deed covenant, easements/right of way, executed maintenance agreement, etc.) | |
| 307 | | | | | | | | d. includes a copy of the mechanism used to ensure long term operation and maintenance of the stormwater management practices (deed covenant, easements/right of way, executed maintenance agreement, etc.). | |
| 308 | | | | | | | | e. includes a copy of the schematics of the practice, with the measurements of design specifications clearly defined | |
| 309 | | | | | | | | f. notes proper frequency of maintenance and includes inspection and maintenance schedule | |
| 310 | | | | | | | | g. includes a maintenance log for tracking and observation | |
| 311 | | | | | | | | h. notes actions to ensure continuous and effective operation of each post construction stormwater practice; | |

| | | | nt Check L tormwater | _ | | n omponents | | | |
|--------|---------------|-------------|----------------------------|---------------|-------------|----------------|-------------|--|----------------------------------|
| 1 0.51 | | PPP Pr | | | | Reviewer(s) | | Post Construction Stormwate | r Management |
| | | | | Consul | ltant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ⊠, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 312 | | | | | | | | TRACKING SPECIFIC DESIGN ELEMENTS: | |
| 313 | | | | | | | | To help track the review of post construction stormwater management practices for require elements, SWPPP reviewers may want to call out practices of concern and note comments. Space is provided here for that purpose. | |
| 314 | | | | | | | | Post Construction Practice #1 Description of Practice: Sizing criteria met, Y/N? Performance criteria met, Y/N? Required elements present, Y/N? Comments? | |
| 315 | | | | | | | | Post Construction Practice #2 Description of Practice: Sizing criteria met, Y/N? Performance criteria met, Y/N? Required elements present,Y/N? Comments? | |
| 316 | | | | | | | | To help track design elements <u>not</u> in conformance with the design criteria in the technical standards, MS4s may want call out specific practices of interest, as follows, and make comments. Space is provided here for that purpose. | |
| 317 | | | | | | | | Non-Conforming Design Element #1 Description: Reason for deviation or alternate design present, Y/N? Info demonstrating that deviation or alternative design is equivalent to standard present, Y/N? Comments: | |

| Part II. | SWPPP | Conter | nt Check L | ist - Long | Versio | n | | | | |
|----------|---------------|-------------|----------------------------|---------------|-------------|------------------|-------------|--|----------------------------------|--|
| D. Post | Construc | ction St | tormwater | Managen | ient Co | omponents | | | | |
| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | Post Construction Stormwater Management | | |
| | | | | Consultant | | MS4 Staff/Others | | Required SWPPP Content | Additional SWPPP Content | |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ⊠, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests | |
| 318 | | | | | | | | Non-Conforming Design Element #2 Description: Reason for deviation or alternate design present, Y/N_? Info demonstrating that deviation or alternative design is equivalent to standard present, Y/N_? Comments: | | |

Part II. SWPPP Content Ck List-Long Version E. Municipal/MS4 Requirements

| | | 1 | | | ·· r ··/· | | | Pertaining to Stormwater Management | |
|------|---------|--------|--------------------|---------------|------------------|-------------|---------|---|--|
| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | Municipal Requirements | |
| Item | ⊠, if | ⊠, if | Item | Consul | ltant | MS4 Staff | /Others | Drawings, Maps, Specifications, Standards | |
| | present | NA | Location (Pg #) | ☑, if present | ⊠, if NA | | | Requested by MS4s | |
| 319 | | | | | | | | Map requirements (can be incorporated into other SWPPP maps) | |
| 320 | | | | | | | | ~project boundary, | |
| 321 | | | | | | | | ~adjacent parcels, | |
| 322 | | | | | | | | ~streets | |
| 323 | | | | | | | | ~adjacent municipalities | |
| 324 | | | | | | | | ~adjacent MS4s of all types | |
| 325 | | | | | | | | Standardization: | |
| 326 | | | | | | | | For stormwater practices which require sizing: Use standard Town of Colonie rainfall amounts for the 1, 2, 10, 25, 50, 100-year 24-hour and 90% rainfall events They are $1-yr = 2.5$ ", $2-yr = 2.8$ ", $10-yr = 4.5$ ", $25-yr = 5.0$ "; $50-yr = 5.8$ "; $100-yr = 7.0$ ", and 90% rainfall (P) = 1.2". | |
| 327 | | | | | | | | RAINFALL AMOUNTS EXPLAINED: To minimize biassed interpretations of isohyet maps in the NYSDEC Stormwater Management Design Manual 2015 and to promote a consistent review of SWPPP applications, the Town of Colonie established rainfall amounts to be applied throughout the Town for all projects. These amounts are based on the NYSDEC 2015 Stormwater Design Manual 2015 isohyet maps in Chapter 4 Uniform Stormwater Sizing Criteria and recommendations from consulting engineers hired by the Town to review SWPPP applications. None of these standardized amounts are lower than all possible 2015 isohyet precipitation amounts for Albany County, and in some cases thery are slightly higher. Also, as stated in teh Design Manual, "Designers may also use the most recent rainfall frequency values developed by acceptable sources. These maps are available online at http://precip.eas.cornell.edu.". For the purposes of this check list, either the Town of Colonie rainfall amounts or the Extreme Precipitation in New York and New England, An Interactive Web Tool for Extreme Precipitation (http://precip.eas.cornell.edu.) dataset is acceptable. | |
| 328 | | | | | | | | Use of City-Town-Village-County-University Standard Specifications (if any) for design of the storm drain system (i.e. catch basins, manholes, piping, etc.) | |
| 329 | | | | | | | | Construction drawings: | |
| 330 | | | | | | | | Stamped construction drawings and SWPPP with the signature and seal of a ' <i>Qualified Professional</i> ', as defined in GP-0-15-002 Construction Activity Permit | |
| 331 | | | | | | | | Location of existing and proposed roadways, lot boundaries, buildings, and other structures | |
| 332 | | | | | | | | Location of existing and proposed utilities (e.g. water, sewer (sanitary and storm), gas, electric) and easements | |
| 333 | | | | | | | | Location of existing and proposed conveyance systems (i.e. swales, MHs, CBs, pipes, etc.) | |
| 334 | | | | | | | | Existing and proposed elevations for storm drain structures (i.e. pipes, CBs, manholes, etc.). Include vertical separation distances for all utilities. | |
| 335 | | | | | | | | Flow paths of surface and subsurface stormwater management structures (use flow arrows) | |
| 336 | | | | | | | | Locations and dimensions of all proposed channel modifications (i.e. bridges & culverts) | |
| 337 | | | | | | | | Final landscaping plans - include buffer zones, reforestation, or wetland mitigation areas | |

Part II. SWPPP Content Ck List-Long Version E. Municipal/MS4 Requirements

| | Part II. SWPPP Content Check List - Long Version E. Municipal Requirements for Drawings, Maps, and Specifications Pertaining to Stormwater Management | | | | | | | | | | | | |
|------|--|--|--|--|-------------------|--|---------|---|--|--|--|--|--|
| | SWPPP Preparer SWPPP Reviewer(s) Municipal Requirements | | | | | | | | | | | | |
| Item | Item Consultant MS4 Staff/Others | | | | | | /Others | Drawings, Maps, Specifications, Standards | | | | | |
| | ⊠, if present | Location I if I if I if I if I if I if | | | Requested by MS4s | | | | | | | | |
| 338 | | | | | | | | Location of sea-level rise projections along Hudson for 2020, 2050, and 2080 ClimAID Supplement Risk Information September, 2014 | | | | | |

| Part I | CONTENT II. SWPPP Content Check List - Short Version | Part III |
|---|---|----------|
| A. Project Parameters | Same content as Part II.A. (Numbering of line items is the same as Part II. SWPPP Content Check List. Where appropriate, content has been abbreviated. | p.2 |
| B. Forms and Documents | Same content as Part II.B. (see above) | p.4 |
| C. Erosion and Sediment Control Components | Same content as Part II.C. (see above) | p.5 |
| D. Post Construction Stormwater Management Components | Same content as Part II.D. (see above) | p.10 |
| E. Municipal Requirements-Maps, Construction Drawings, Standards | Same content as Part II.E. (see above) | p.19 |

Part III. SWPPP Content Check List-Short Version A. Project Parameters

| Part III. | . SWPPF | P Conte | ent Check | List - Sho | rt Versi | ion | | | | | | |
|-----------|--|---------|--------------------|---------------|-------------|----------------------|-------------|---|--|--|--|--|
| A. Proje | A. Project Parameters (location; project activities; site geography; reg features; E-SC Only or E-SC & Post C.) SWPPP Preparer SWPPP Reviewer(s) Project Information | | | | | | | | | | | |
| | SW | PPP Pr | eparer | S | WPPP | Reviewer(s) | | Project Information | | | | |
| Item | ⊠, if | ⊠, if | Item | Consu | ltant | ant MS4 Staff/Others | | | | | | |
| | present | NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | SWPPP Contents | | | | |
| 1 | | | | | | | | 1. General Information | | | | |
| 2 | | | | | | | | a. Project name | | | | |
| 3 | | | | | | | | b. Project location (which municipality) | | | | |
| 4 | | | | | | | | c. Project location (tax map numbers-Section/Block/Lot) | | | | |
| 5 | | | | | | | | d. Project location (latitude and longitude) | | | | |
| 6 | | | | | | | | e. Project address (if available) | | | | |
| 7 | | | | | | | | f. Name of project owner or operator | | | | |
| 8 | | | | | | | | g. Address of project owner or operator | | | | |
| 9 | | | | | | | | h. If SWPPP MS4 Acceptance Form required, name of MS4 | | | | |
| 10 | | | | | | | | 2. Project Specifics | | | | |
| 11 | | | | | | | | a. General overview (purpose and extent of proposed development). | | | | |
| 12 | | | | | | | | b. Project area (acres) | | | | |
| 13 | | | | | | | | d. Description of project type (E/SC or E/SC and post construction stormwater practices) | | | | |
| 14 | | | | | | | | e. Project type is stated clearly given Construction Activity Permit (Appendix E) and MS4 Permit (Appendix 2). | | | | |
| 15 | | | | | | | | f. Project type states whether or not it is New Development, New Development in an Enhanced Phosphorus Removal Watershed, Redevelopment Activity, or Redevelopment Activity and New Development. | | | | |
| 16 | | | | | | | | g. If Redevelopment Activity, status of impervious area (will decrease, increase, or stay the same) noted. | | | | |
| 17 | | | | | | | | h. SWPPP states the local law by number and date which triggers submission of SWPPP; and names required local municipal permits for clearing, grubbing, grading, or excavating. | | | | |
| 18 | | | | | | | | i. SWPPP describes which infrastructure (separated or combined) will receive stormwater runoff from project, describes which local laws, design criteria, and/or regulatory requirements will guide project design. | | | | |
| 19 | | | | | | | | j. For projects owned by the MS4, describe any policy documents used to guide the design of post construction stormwater practices. | | | | |
| 20 | | | | | | | | k. List all of the practices proposed for this site. | | | | |

Part III. SWPPP Content Check List-Short Version A. Project Parameters

| Part III | . SWPPF | P Conte | ent Check | List - Shoi | rt Versi | on | | |
|----------|---------------|--------------|--------------------|---------------|-------------|---------------|-------------|--|
| A. Proje | ect Parar | neters | (location; p | roject activ | vities; si | ite geograph | ıy; reg fe | eatures; E-SC Only or E-SC & Post C.) |
| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | Project Information |
| Item | | 1 : F | Item | Consul | ltant | MS4 Staff | Others | |
| | ☑, if present | ⊠, if NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | SWPPP Contents |
| 21 | | | | | | | | 3. Physical Geography; Regulatory Features; Eligibility for General Permit Coverage |
| 22 | | | | | | | | a. Name of all waterbodies receiving stormwater discharges from this site |
| 23 | | | | | | | | b. Stream classification of initial receiving waters of construction activity discharges. |
| 24 | | | | | | | | c. Regulatory status of initial receiving water of construction activity discharges |
| 28 | | | | | | | | d. If project discharges directly to separated storm sewer systems, name of owner? If MS4, name of MS4.? |
| 29 | | | | | | | | e. Description, if any of land areas where Soil Slope Phase is identified as an E or F, or the map unit is inclusive of 25% of greater slope on the USDA Soil Survey for the County. |
| 30 | | | | | | | | f. Description, if any of construction activities or discharges that may adversely affect an endangered or threatened species and actions taken to address issue. |
| 31 | | | | | | | | g. Description, if any of construction activities that have the potential to affect an historic property and actions taken to address the issue. |
| 32 | | | | | | | | h. Description of natural features influencing construction and maintenance of erosion and sediment controls (site slopes; soil erobility/K-value; infiltration rate; type of soils) |
| 33 | | | | | | | | i. Description of natural features influencing design of post construction practices |
| 34 | | | | | | | | j. Description of man-made features influencing design of post construction practices |
| 35 | | | | | | | | k. Description, if any of stormwater hotspots associated with the intended land use or activity of project. |
| 37 | | | | | | | | 4. General Permit Coverage for Construction Activity |
| 38 | | | | | | | | a. Statement affirming that this land disturbance project is eligible for general permit coverage under NYSDEC SPDES GP-0-15-002 Construction Activity Permit. |

Part III. SWPPP Content Check List-Short Version B. Forms and Documents

| Part III. | . SWPPP | P Conte | ent Check | List - Shoi | rt Versi | on | | |
|-----------|---------------|-------------|--------------------|---------------|-------------|---------------|-------------|--|
| B. Form | s and Do | ocumer | nts to Subn | nit With S | WPPP | | | |
| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | SWPPP Related Documents |
| Item | | | Item | Consul | tant | MS4 Staff | /Others | |
| | ⊠, if present | ⊠, if NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Description |
| 49 | | | | | | | | 1. Construction Activity Permit Forms |
| 50 | | | | | | | | a. Notice of Intent (NOI) Form |
| 51 | | | | | | | | b. Notice of Intent (eNOI) Submission Form. |
| 52 | | | | | | | | c. SWPPP Preparer Certification Form |
| 53 | | | | | | | | d. Owner/Operator Certification Form |
| 54 | | | | | | | | e. Contractor and Sub Contractor Certification Form |
| 55 | | | | | | | | f. Notice of Termination (NOT) Form |
| 56 | | | | | | | | 2. MS4 Permit Forms Related to Oversight of Construction Activity Permit |
| 57 | | | | | | | | a. MS4 SWPPP Acceptance Form |
| 58 | | | | | | | | <i>b. Notice of Termination (NOT) Form</i> (filled in as much as possible for MS4) |
| 59 | | | | | | | | c. MS4 Construction Site Inspection Form (not filled in) |
| 60 | | | | | | | | d. Blank copy of owner or operator: Contractor Maintenance Inspection Report Form |
| 61 | | | | | | | | e. Blank copy of owner or operator: "Qualified Inspector" Inspection Report Form |
| 62 | | | | | | | | 3. Other Documents Named in Construction Activity Permit (GP-0-15-002) |
| 63 | | | | | | | | a. State Historic Preservation Act (SHPA) |
| 79 | | | | | | | | b. State Environmental Quality Review Act ("SEQRA") |
| 81 | | | | | | | | c. Uniform Procedures Act ("UPA") |
| 102 | | | | | | | | d. Federal Permits |
| 103 | | | | | | | | i. Underground Injection Control Permit |
| 105 | | | | | | | | ii. Army Corps of Engineers-Wetland Permits |
| 106 | | | | | | | | 4. Documents Pertaining to Post Construction Stormwater Management Practices (Required by land use control MS4) |
| 107 | | | | | | | | All necessary stormwater easement documentation, if applicable. |
| 108 | | | | | | | | Maintenance Agreement |

| ItemItem \overline{M} , if presentItem \overline{NA} ConsultantMS4 Staff/OthersRequired SWI Required SWI \overline{M} , if presentText from Construction 0-154110Image: Start Sta | | |
|--|---|--|
| Item $\overline{\mathbb{P}}$, if $\overline{\mathbb{P}}$, if $\overline{\mathbb{P}}$, if $\overline{\mathbb{N}}$, $\overline{\mathbb{N}}$ Item $\overline{\mathbb{N}}$, if $\overline{\mathbb{N}}$, if $\mathbb{N$ | | |
| Image: Book of the presentNALocation (Pg #) \overline{U} , if present \overline | Erosion and Sediment Contr | ol Components |
| presentNALocation ($Pg \neq$) \vec{P} , if present \vec{P} , if present \vec{P} , if present \vec{P} , if present \vec{P} , if \vec{NA} \vec{P} , if present \vec{NA} Text from Construction $0-154$ 110IIIIIIIIIIIII111IIIIIIIIIIIII111IIIIIIIIIIIII112II </td <td>ed SWPPP Content</td> <td>Additional SWPPP Content</td> | ed SWPPP Content | Additional SWPPP Content |
| 111 At a minimum, the eros control component of the include the following: 111 Background info about including location, type 112 Background info about including location, type 116 Project, including a gen project a gen project, including a gen project, including a gen project, | ruction Activity Permit GP- 0-15-002 | - MS4 Clarificatons & Requests |
| 111 control component of the include the following: 112 Background info about including location, type 116 Site map/construction of project, including a gen 117 At a minimum, the sit 118 At a minimum, the sit 119 At a minimum, the sit 120 areas of disturbance 121 areas of disturbance 122 areas of disturbance 123 areas of disturbance 124 areas of disturbance 125 areas of disturbance 126 areas of disturbance 127 areas of disturbance 128 areas of disturbance 129 areas of disturbance 130 areas of disturbance 131 areas of disturbance | | If construction activity is a single family home, use Appendix E Erosion and Sediment Control Plan for Small Homesite Construction from the NYS Standards and Specifications for Erosion and Sediment Control dated August, 2005 or provide equivalent details and specifications. |
| 112 including location, type 116 Site map/construction of project, including a gen project, including | | |
| 110 project, including a gen 117 At a minimum, the sit 118 the total site area; 119 all improvements; 120 areas of disturbanc 121 areas of disturbanc 122 areas of disturbanc 123 areas of disturbanc 124 on-site and adjacer 125 areas that will not 126 areas that will not 127 areas that will not 128 areas that will not 129 areas that will not 130 areas that will not 133 areas that will not | about: scope of project, n, type, and size of project. | |
| 117 At a minimum, the sit 118 the total site area; 119 areas of disturbance 120 areas of disturbance 121 areas of disturbance 122 areas that will not 123 areas that will not 124 areas that will not 124 areas that will not 125 areas that will not 126 areas that will not 127 areas that will not 128 areas that will not 129 areas that will not 131 areas that will not | ction drawing(s) for the g a general location map. | |
| 119 -all improvements; 120 -areas of disturbance 121 -areas of disturbance 122 -areas that will not 122 -areas that will not 123 -areas that will not 124 -areas that will not 125 -floodplain/floodwa 126 -areas that will not 127 -areas that will not 126 -areas that will not 127 -areas that will not 128 -areas that will not 129 -areas that will not 131 -areas that will not 133 -areas that will not | the site map shall show: | |
| 120 ~areas of disturbance 121 ~areas that will not 122 ~areas that will not 122 ~areas that will not 123 ~areas that will not 124 ~areas that will not 124 ~floodplain/floodwa 124 ~areas that will not 125 ~areas that will not 126 ~areas that will not 127 ~areas that will not 126 ~areas that will not 127 ~areas that will not 128 ~areas that will not 129 ~areas that will not 130 ~areas that will not 131 ~areas that will not 133 ~areas that will not | | |
| 121 -areas that will not 122 -on-site and adjacer 123 -floodplain/floodwa 124 -areas that will not 124 -areas that will not 124 -areas that will not 125 -areas that will not 126 -areas that will not 127 -areas that will not 128 -areas that will not 129 -areas that will not 130 -areas that will not 131 -areas that will not | | |
| 122 | | |
| 122 water(s); 123 -floodplain/floodwa 124 -wetlands and drain could be affected by activity; 125 -existing and final of activity; 126 -existing and final of activity; 127 -locations of differen boundaries; 128 -notations of differen boundaries; 129 -material waste, born storage areas located of properties; 130 -material waste, born storage areas located of properties; 131 -material waste, born storage areas located of properties; 133 -material waste, born storage areas located of properties; | | |
| 124 -wetlands and drain could be affected by activity; 125 -existing and final of activity; 126 -vecisiting and final of activity; 126 -locations of differen boundaries; 127 -vecisiting and set, borres; 128 -vecisiting areas located of properties; 129 -vecisiting areas located of properties; 131 -vecisiting areas located of properties; 132 -vecisiting areas located of properties; 133 -vecisiting areas located of properties; | adjacent off-site surface | |
| 124 could be affected by activity; 125 -existing and final of existing and final | loodway boundaries; | |
| 126 -locations of different boundaries; 127 -locations of different boundaries; 128 -material waste, borros storage areas located of properties; 129 -interval 130 -interval 131 -interval 132 -interval 133 -interval | d drainage patterns that cted by the <i>construction</i> | |
| 127 -locations of differen boundaries; 128 -material waste, borres; 128 -material waste, borres; 129 -material waste, borres; 130 -material waste, borres; 131 -material waste, borres; 132 -material waste, borres; | final contours; | |
| 127 boundaries; 128 ~material waste, borro storage areas located of properties; 129 | | ~existing and final proposed topography a minimum of 50' beyond the property (min. 2'contours) or as required by MS4 |
| 128 storage areas located oproperties; 129 non-storage 130 non-storage 131 non-storage 132 non-storage 133 non-storage | ifferent soil types with | |
| 130 | e, borrow, or equipment ocated on adjacent | |
| 131 132 133 133 | | Specific details for: |
| 132 133 | | ~material stockpiling |
| 133 | | ~equipment staging |
| | | ~material storage |
| | | ~borrow/spoil areas |
| | | ~dewatering operations |
| 135 136 | | ~spill/waste containment ~concrete wash-out |

| | | | ent Check l nt Control | | | ion | | | |
|------|---------------|-------------|---------------------------|---------------|-------------|---------------|-------------|---|---|
| | | PPP Pr | | | | Reviewer(s) | | Erosion and Sediment Contro | ol Components |
| Item | EX :f | LA :t | Item | Consul | ltant | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| | ☑, if present | ⊠, if NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 | MS4 Clarificatons & Requests |
| 137 | | | | | | | | ~location(s) of stormwater <i>discharge(s)</i> ; | |
| 138 | | | | | | | | | ~boundary of the proposed limits of clearing and, if different, limits of grading on the site. |
| 139 | | | | | | | | A description of the soil(s) present at the site, including identification of the Hydrological Soil Group. | |
| 140 | | | | | | | | Construction phasing plan and sequence of operations describing the intended order of <i>construction activities</i> , including: | Phasing plan must limit active disturbance to under 5 acres. |
| 141 | | | | | | | | ~clearing and grubbing; | |
| 142 | | | | | | | | ~excavation and grading; | |
| 143 | | | | | | | | ~utility and infrastructure installation; | |
| 144 | | | | | | | | ~any other activity at the site that results in soil disturbance | |
| 145 | | | | | | | | | ~stockpiling |
| 146 | | | | | | | | | ~final stabilization |
| 147 | | | | | | | | A description of the minimum erosion and sediment control practices to be installed or implemented Include a schedule that: | |
| 148 | | | | | | | | ~ identifies the timing of initial placement or implementation of each erosion and sediment practice and; | |
| 149 | | | | | | | | ~the minimum time frames that each practice should remain in place or be implemented. | |
| 150 | | | | | | | | A temporary and permanent soil stabilization plan | |
| 151 | | | | | | | | | Specifications for temporary and permanent seeding – note seed types and application rates |
| 152 | | | | | | | | | Statement which reads that in areas where soil activity has temporarily or permanently ceased, the application of soil stabilization measures must be initiated by the end of the next business day and completed within fourteen (14) days from the date the current soil disturbance activity ceased. |

Project: _____ Date:_____

| | | | ent Check | | | on | | | |
|----------|--|-------|------------------|-----------------|---------------|--------------------|-----------------|--|---|
| C. Erosi | ion and Sediment Contr SWPPP Preparer | | | | | Reviewer(s) | | Erosion and Sediment Contro | ol Components |
| | 511 | | eparer | | | | /0.1 | | |
| Item | ⊠, if | ⊠, if | Item Location | Consul ☑, if | tant ⊠, if | MS4 Staff ☑, if | Øthers ☑, if | Required SWPPP Content Text from Construction Activity Permit GP- | Additional SWPPP Content MS4 Clarificatons & |
| | present | NA | (Pg #) | present | NA | present | NA | 0-15-002 | Requests |
| 153 | | | | | | | | | For construction sites that directly discharge to one of the 303(d) listed segments in Appendix E, a statement which reads that the application of soil stabilization measures must be initiatiated by the end of the next business day and completed within seven (7) days from the date the current soil disturbance activity ceased. |
| 154 | | | | | | | | A site map/construction drawing(s) showing the specific location(s), size(s), and length(s) of each erosion and sediment control practice | |
| 155 | | | | | | | | | Descriptions of structural practices used to divert flows |
| 156 | | | | | | | | The dimensions, material specifications, installation details, and operation and maintenance requirements for all erosion and sediment control practices. | |
| 157 | | | | | | | | | Calculations for siting and sizing of any temporary sediment basins and/or traps |
| 158 | | | | | | | | | Identification of any maintenance or inspection actions that are required prior to converting practices to permanent control measures |
| 159 | | | | | | | | A maintenance inspection schedule for the contractor(s) | |
| 160 | | | | | | | | A description of the pollution prevention measures that will be used | |
| 164 | | | | | | | | | Description of construction and waste materials expected to be utilized on-site or adjacent to site |
| 165 | | | | | | | | | Description of controls to reduce pollutants from these materials |
| 166 | | | | | | | | | Description of cleanup procedures and spill prevention and notification for each material |

| | | | ent Check] nt Control | | | ion | | | | |
|---------|---------------|-------------|---------------------------|---------------|-------------|---------------|-------------|--|---|--|
| C. Eros | | PPP Pr | | | | Reviewer(s) | | Erosion and Sediment Contro | ol Components | |
| Item | | | Item | Consul | | MS4 Staff | | Required SWPPP Content | Additional SWPPP Content | |
| | ⊠, if present | ⊠, if NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 | MS4 Clarificatons & Requests | |
| 167 | | | | | | | | A description and location of any stormwater discharges associated with industrial activity | | |
| 168 | | | | | | | | Identification of any elements of the design that are not in conformance with the design criteria in the technical standard | | |
| 169 | | | | | | | | ~include the reason for the deviation or alternative design | | |
| 170 | | | | | | | | ~provide information which demonstrates that the deviation or alternative design is equivalent to the standard. | | |
| 171 | | | | | | | | | If project is in a regulated MS4, description of winter month, October 15 to April 15, requirements related to E&SC (i.e. anchoring mulch material, sediment removal from basins/traps, use of winter rye seed, offset silt fence, etc.). See Winter Shutdown and Site Inspection Requirements available from MS4. | |
| 172 | | | | | | | | TRACKING SPECIFIC DESIGN ELEMENTS: | | |
| 173 | | | | | | | | To help track the review of E/SC practices for presence/absence, size, and length information, MS4s may want to call out practices of concern and note comments. Space is provided here for that purpose. | | |
| 174 | | | | | | | | E/SC Practice #1 Description of Practice: Location present, Y/N? Size present Y/N? Length present, Y/N? Comments: | | |
| 176 | | | | | | | | To help track the review of each E/SC practice for presence/absence of dimension, material specification, installlation details, and operation and maintenance requirements for erosion and control practices MS4s may want to call out specific practices of interest and make comments. Space is provided here for that purpose. | | |

| | | | ent Check I | | | on | | | | |
|----------|-----------|--------|--------------------|---------------|-------------|------------------|-------------|--|---------------------------------|--|
| C. Erosi | ion and S | Sedime | nt Control | Compone | ents | | | | | |
| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | Erosion and Sediment Control Components | | |
| Item | ⊠, if | ⊠, if | Item | Consul | tant | MS4 Staff/Others | | Required SWPPP Content | Additional SWPPP Content | |
| | present | NA | Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP- 0-15-002 | MS4 Clarificatons & Requests | |
| 177 | | | | | | | | E/SC Practice #1 Description of Practice | | |
| 179 | | | | | | | | To help track design elements <u>not</u> in conformance with the design criteria in the technical standards, MS4s may want call out specific practices of interest, as follows, and make comments. Space is provided here for that purpose. | | |
| 180 | | | | | | | | Non-Conforming Design Element #1 Description: Reason for deviation or alternate design present, Y/N? Info demonstrating that deviation or alternative design is equivalent to standard present, Y/N? Comments: | | |

| | CW | | | C | | Darrianuar(a) | | Dest Construction Storm | watan Managamant |
|------|------------------|-------------|----------------------------|---------------|-------------|------------------|-------------|--|---|
| | 5₩ | PPP Pre | eparer | 3 | WPPP | Reviewer(s) | | Post Construction Storm | water Management |
| Itam | | ⊠, if NA | T. | Consul | ltant | MS4 Staff/Others | | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 182 | | | | | | | | From Construction Activity Permit: | |
| 183 | | | | | | | | Post-construction stormwater management component- | |
| 185 | | | | | | | | The post-construction stormwater management practice component of the SWPPP shall include the following: | |
| 186 | | | | | | | | Identification of all post-construction stormwater management practices | |
| 187 | | | | | | | | A site map/construction drawing(s) | |
| 188 | | | | | | | | Stormwater Modeling and Analysis Report that includes: | |
| 189 | | | | | | | | ~Map(s) showing pre-development conditions, | Watershed/sub-catchment include any upstream watersheds draining onto the project site and the associated stormwater collection and conveyance structures |
| 190 | | | | | | | | ~Map(s) showing post-development conditions | Watershed/sub-catchment include any upstream watersheds draining onto the project site and the associated stormwater collection and conveyance structures |
| 191 | | | | | | | | ~Results of stormwater modeling (i.e. hydrology and hydraulic analysis) | |
| 192 | | | | | | | | ~Summary table, with supporting calculations | |
| 193 | | | | | | | | ~Identification of any sizing criteria that is not required | |
| 194 | | | | | | | | ~Identification of any elements of the design that are not in conformance with the <i>performance criteria</i> | |
| 195 | | | | | | | | Soil testing results and locations (test pits, borings) | Testing is conducted in conformance with the NYS Stormwater Management Design Manual (2015) Appendix D. |
| 196 | | | | | | | | Infiltration results, when required, in particular at location of stormwater management practices. | |
| 197 | | | | | | | | From Construction Activity Permit: | |
| 198 | | | | | | | | If Enhanced Phosphorus Removal Watershed(s): (NA for Albany County) | |

| - | |
|------|----|
| Date | ٠ |
| Date | ۰. |

| | | | ent Check | | | omponents | | - | | |
|------|---------------|-------------|----------------------------|------------------|-------------|------------------|-------------|---|---|--|
| | SW | PPP Pr | eparer | S | WPPP | Reviewer(s) | | Post Construction Stormwater Management | | |
| | | | | Consul | ltant | MS4 Staff/Others | | Required SWPPP Content | Additional SWPPP Content | |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests | |
| 200 | | | | | | | | Chapter 3 Stormwater Management Planning Requirements (Five Step Process) | MS4 Requests & Clarifications | |
| 201 | | | | | | | | Planners and designers must address this approach (<i>i.e. stormwater management</i> <i>planning</i>) in a step-wise process that involves site planning and stormwater management practice (SMP) selection. This includes providing information in the SWPPP which documents compliance with the required process. The steps include: | | |
| 202 | | | | | | | | The Six Step Process for Stormwater Site Planning and Practice Selection | | |
| 203 | | | | | | | | Step 1 Site Planning | | |
| 204 | | | | | | | | | Text or chart which describes how Preservation of Natural Resources practices have been incorporated into the SWPPP Stormwater Management Plan. | |
| 213 | | | | | | | | | Text or chart which describes how Reduction of Impervious Cover practices have been incorporated into the SWPPP Stormwater Management Plan. | |
| 222 | | | | | | | | The SWPPP must include an evaluation of all green infrastructure planning measures as they apply to the site. The evaluation process requires the following measures: | | |
| 223 | | | | | | | | 1. Developing a map that identifies natural resource areas and drainage patterns, including, but not limited to: | | |
| 224 | | | | | | | | ~Wetlands (jurisdictional, wetland of special concern) | | |
| 226 | | | | | | | | ~Waterways (major, perennial, intermittent, springs) | | |
| 227 | | | | | | | | ~Buffers (stream, wetlands, forest, etc.) | | |
| 228 | | | | | | | | ~Floodplains | ~Map includes100-yr floodplain and floodway limits if disturbance proposed is in the floodplain | |
| 229 | | | | | | | | ~Forest, vegetative cover | ~Map includes description and boundaries of the existing predominant vegetative cover on the project site | |

| | | | ent Check | | | | | | |
|---------|---------------|-------------|----------------------------|---------------|-------------|---------------|-------------|---|--|
| D. Post | | PPP Pr | tormwater eparer | | | Reviewer(s) | | Post Construction Storm | water Management |
| | | | | Consul | ltant | MS4 Staff | Others | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 230 | | | | | | | | ~Critical areas | ~Map includes location and boundaries of resource protection areas (water supply well setbacks, septic system setbacks, sole source aquifers, etc.) |
| 231 | | | | | | | | ~Topography (contour lines, existing flow paths, steep slopes, etc.) | ~Map includes existing topography a minimum of 50' beyond the property (min. 2'contours), or as required by MS4 |
| 232 | | | | | | | | ~Soil (hydrological groups, highly erodible soils, etc.) | ~Map includes description and map of all soils on the site (HSG, highly erodible soils, E and F Soil Slope Phase, others) |
| 233 | | | | | | | | ~Bedrock, significant geological features | ~Map notes location of karst bedrock, if any |
| 234 | | | | | | | | | ~If project near Hudson River, map notes location of sea-level rise projections along Hudson for 2020, 2050, and 2080 ClimAID Supplement Risk Information September, 2014 (Rule making pending-Community Risk and Resiliency Act) |
| 235 | | | | | | | | 2. Devising the strategies for protection and enhancement of natural resources | |
| 240 | | | | | | | | 3. Reduce the impacts of development by reducing impervious surfaces | |
| 241 | | | | | | | | 4. Demonstrating that all reasonable opportunities for preserving natural conditions of the site are employed | |
| 242 | | | | | | | | During the planning step, the designer should check with municipalities to determine if there are local laws and ordinances that regulate wetlands, stream buffers, forest or habitat protection, erosion control or grading. The designer should also consult the municipalilty for laws relating to conservation or cluster design, roads, driveways, and parking lots to determine level of flexibility in reducing impervious surfaces. | SWPPP acknowledges and complies with applicable local laws . |

| Part III. | SWPPF | Conte | ent Check I | List - Shor | rt Versi | on | | | | |
|-----------|----------|--------------|----------------------------|---------------|-------------|------------------|-------------|---|---|--|
| D. Post | Construe | ction St | tormwater | Managen | ient Co | mponents | | | | |
| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | Post Construction Stormwater Management | | |
| _ | | | Item Location (Pg #) | Consultant | | MS4 Staff/Others | | Required SWPPP Content | Additional SWPPP Content | |
| Item | · · | ⊠, if NA | | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests | |
| 243 | | | | | | | | Step 2 Determine Water Quality Treatment Volume (WQv) | | |
| 244 | | | | | | | | The designer calculates the required WQv for the site using criteria in Chapter 4. Once the preliminary site layout is prepared: | | |
| 245 | | | | | | | | ~impervious areas are defined | SWPPP calculates impervious area using Design Manual Chapter 4 definition. Total area, impervious area, % impervious calculated for each sub-catchment. % impervious used in WQv calculations. | |
| 246 | | | | | | | | ~sub-catchments are delineated | SWPPP text and related maps identify the sub-catchments used to calculate water quality volume (WQv). | |
| 247 | | | | | | | | ~designer calculates the water quality volume | Water quality volume calculations matched to sub-catchment and impervious areas. | |

| | | | ent Check | | | ion omponents | | | |
|----------|---------------|-------------|----------------------------|---------------|-------------|------------------|-------------|---|--|
| D. I USU | | PPP Pr | | | | Reviewer(s) | | Post Construction Storm | water Management |
| | | | | Consul | | MS4 Staff | | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 248 | | | | | | | | Step 3 Apply Runoff Reduction Techniques and Standards SMPs with RRv Capacity (e.g. infiltration practices, bioretention, open channel practices) to Reduce Total WQv | |
| 249 | | | | | | | | | SWPPP includes a thorough and clear analysis of: |
| 250 | | | | | | | | | 1) how the require total WQv was calculated; |
| 251 | | | | | | | | | 2) description and calculation of minimum runoff reduction requirement; |
| 252 | | | | | | | | | 3) description of runoff reduction calculations for each of the techniques listed in Table 3.2 and SWPs with RRV capacity; |
| 253 | | | | | | | | | 4) reason why a particular runoff reduction technique or techniques were selected by the designer; |
| 254 | | | | | | | | | 5) reasons why a particular runoff reduction technique was not selected; and |
| 255 | | | | | | | | | 6) for redevelopment projects use of any runoff reduction techniques, if any |
| 271 | | | | | | | | If the standard SMPs with RRv capacity listed above are used to address RRv criteria, the practices must be designed to capture runoff at the source. | SWPPP text describes location of any standard SMPs with RRv |
| 272 | | | | | | | | | SWPPP text states clearly based on calculated values documented in the SWPPP (runoff reduction worksheets) that the RRv value is greater than or equal to WQv value. |
| 273 | | | | | | | | | If runoff reduction volume can not be met, SWPPP states clearly specific site limitations related to all possible runoff reduction techniques. Explanation references data from soil borings, test pits, and infiltration tests. |

| | | | ent Check I tormwater | | | | | | |
|----------|---------------|-------------|----------------------------|---------------|-------------|------------------|-------------|--|---|
| D. 1 051 | | PPP Pr | | | | Reviewer(s) | | Post Construction Storm | water Management |
| | | | | Consul | ltant | MS4 Staff/Others | | Required SWPPP Content | Additional SWPPP Content |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 274 | | | | | | | | | If designer can not reduce 100% of the WQv due to site limitations, the SWPPP states which runoff reduction techniques or standard SMP with RRv capacity will be used unless infeasible. |
| 275 | | | | | | | | Step 4 Determine the minimum RRv | |
| 276 | | | | | | | | required | SWPPP text describes how the minimum RRv was calculated. |
| 277 | | | | | | | | Step 5 Apply Standard Stormwater Management Practices to Address Remaining Water Quality Volume | |
| 278 | | | | | | | | | SWPPP text describes how much of the water quality volume will be treated using runoff reduction techniques or SMPs with RRv capacity and describes which standard SMPs will be used to treat the remaining WQv. Text verifies that RRv requirement has been met. |
| 279 | | | | | | | | Step 6 Apply Volume and Peak Rate Control Practices if Still Needed to Meet Requirements | |
| 280 | | | | | | | | | SWPPP text describes which channel protection; overbank flood control, and extreme flood controls will be used to meet water quantity requirements, as needed. |
| 281 | | | | | | | | Criteria for Practice Addition | |
| 282 | | | | | | | | | SWPPP text, as needed describes alternate stormwater management practices in new construction. Description includes all relevant explanations regarding equivalency, required performance and sizing criteria, and requirements related to proprietory practices. |

| D. Post | Construc | cuon o | | | | - | | | | |
|---------|---------------|-------------|----------------------------|---------------|-------------|------------------|-------------|--|---|--|
| | SW | PPP Pr | eparer | S | WPPP I | Reviewer(s) | | Post Construction Stormwater Management | | |
| | | | | Consul | ltant | MS4 Staff/Others | | Required SWPPP Content | Additional SWPPP Content | |
| Item | Ø, if present | ⊠, if NA | Item Location (Pg #) | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests | |
| 286 | | | | | | | | Exceptions to Meeting the Runoff Reduction Volume (RRV) Criteria: | | |
| 287 | | | | | | | | | If project is a redevelopment activity, SWPPP text explains Chapter 9 criteria and status of this project for meeting RRv criteria. | |
| 288 | | | | | | | | | If project is located in area with karst geology, SWPPP text explains results of recommended geotechnical assessment, the need to avoid large infiltration basins; and explains why and which runoff reduction techniques are included in the SWPPP. | |
| 289 | | | | | | | | | If project activity will result in or include any of the NYSDEC stormwater hotspots, the SWPPP describes which non-infiltration type practices will be used to meet the RRv criteria. | |
| 290 | | | | | | | | Chapter 9 Redevelopment Activity NYSDEC Stormwater Management Design Manual-2015 | MS4 Requests & Clarifications | |
| 291 | | | | | | | | Determinations regarding waiver of water quantity requirements: | | |
| 292 | | | | | | | | 10- and 100-year water quantity control criteria waived | Calculations indicating no alteration of hydrology that would increase discharge rate (ref. Results of stormwater modeling, Ck List Item No.188. | |
| 293 | | | | | | | | Channel protection water quantity control criteria waived because no change in hydrology | Calculations showing that the post construction 1-yr 24-hour discharge rate and velocity will no exceed the pre-construction condition (ref. Results of Stormwater Modeling: Ck List Item No. 188) | |

| Part III. SWPPP Content Check List - Short Version | | | | | | | | | | | |
|--|------------------|----------------|----------------------------|---------------|-------------|------------------|-------------|---|--|--|--|
| D. Post | Construe | ction St | tormwater | Managen | ient Co | mponents | | | | | |
| Item | SW | SWPPP Preparer | | | WPPP I | Reviewer(s) | | Post Construction Storm | Post Construction Stormwater Management | | |
| | ☑, if present | ⊠, if NA | Item Location (Pg #) | Consultant | | MS4 Staff/Others | | Required SWPPP Content | Additional SWPPP Content | | |
| | | | | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests | | |
| 294 | | | | | | | | Treatment is required for 100% of runoff from newly created impervious surfaces and 25% of redeveloped (pre-existing) impervious surfaces | Calculation of the water quality volume with separate components for new impervious surfaces and reconstructed impervious surfaces (ref. Step 2, Determine Water Quality Treatment Volume: Ck List Item No. 188) | | |
| 295 | | | | | | | | Option selected for meeting the water quality criteria for redeveloped portions of site (or all of site if no increase in impervious): | | | |
| 296 | | | | | | | | Impervious cover at close of construction reduced by at least 25% of the total disturbed impervious area, with soil restoration in newly created pervious areas | Site plans clearly indicate areas converted from impervious to pervious conditions and text/narrative shows acreages or square footage reduced | | |
| 297 | | | | | | | | A minimum of 25% of the WQv from the disturbed impervious area is captured and treated by standard practices or reduced by runoff reduction techniques. | Site plans show location of standard or runoff reduction practices and indicate the contributing drainage areas to them. | | |
| 298 | | | | | | | | Alternative ("proprietary") practices will treat 75% of the WQv from the disturbed impervious area as well as any additional runoff from tributary areas outside the disturbed impervious area. | Site plans show location of proprietary practices and drainage areas to them, and list the manufacturer and model for validation that the technology is accepted by NYSDEC. | | |
| 299 | | | | | | | | A combination of the above three approaches is proposed and weighted using the following formula: %WQv treatment by Altnerative practice = (25 - (%IC reduction + WQv treatment by Standard practice + % Runoff reduction)) x 3 | If this formula is used to determine the proportion of the WQv that must be handled by alternative practice, inputs to the calculation should be provided with supporting data. | | |

| | | | ent Check | | | omponents | | - | |
|------|----------------|--|-----------|---------------|-------------|------------------|-------------|---|-------------------------------|
| | SWPPP Preparer | | | S | WPPP I | Reviewer(s) | | Post Construction Stormy | water Management |
| Item | | | | Consultant | | MS4 Staff | /Others | Required SWPPP Content | Additional SWPPP Content |
| | ☑, if present | | LOCATION | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Text from Construction Activity Permit GP-0-15-002 or NYS Stormwater Management Design Manual (2015) Chapters 3 & 9 | MS4 Clarifications & Requests |
| 300 | | | | | | | | From Construction Activity Permit: | |
| 302 | | | | | | | | Chapter 3 Stormwater Management Planning (Operations & Maintenance Plan) | |
| 303 | | | | | | | | Operations and maintenance plan, which | |
| 312 | | | | | | | | TRACKING SPECIFIC DESIGN ELEMENTS: | |
| 313 | | | | | | | | To help track the review of post construction stormwater management practices for require elements, SWPPP reviewers may want to call out practices of concern and note comments. Space is provided here for that purpose. | |
| 314 | | | | | | | | Post Construction Practice #1 Description of Practice: Sizing criteria met, Y/N? Performance criteria met, Y/N? Required elements present, Y/N? Comments? | |
| 316 | | | | | | | | To help track design elements <u>not</u> in conformance with the design criteria in the technical standards, MS4s may want call out specific practices of interest, as follows, and make comments. Space is provided here for that purpose. | |
| 317 | | | | | | | | Non-Conforming Design Element #1 Description: Reason for deviation or alternate design present, Y/N? Info demonstrating that deviation or alternative design is equivalent to standard present, Y/N? Comments: | |

Part III. SWPPP Content Ck List-Short Version E. Municipal/MS4 Requirements

| Date |
|------|
| |

| Part III | Part III. SWPPP Content Check List - Short Version | | | | | | | |
|----------|--|----------------|----------------------------|---------------|-------------|------------------|-------------|--|
| E. Mun | icipal Re | quiren | nents for Di | rawings, N | laps, an | d Specificat | ions Per | taining to Stormwater Management |
| | SW | SWPPP Preparer | | | WPPP I | Reviewer(s) | | Municipal Requirements |
| Item | ☑, if present | ⊠, if NA | Item Location (Pg #) | Consultant | | MS4 Staff/Others | | Drawings, Maps, Specifications, Standards |
| | | | | ☑, if present | ⊠, if NA | ☑, if present | ⊠, if NA | Requested by MS4s |
| 319 | | | | | | | | Map requirements (can be incorporated into other SWPPP maps) |
| 320 | | | | | | | | ~project boundary, |
| 321 | | | | | | | | ~adjacent parcels, |
| 322 | | | | | | | | ~streets |
| 323 | | | | | | | | ~adjacent municipalities |
| 324 | | | | | | | | ~adjacent MS4s of all types |
| 325 | | | | | | | | Standardization: |
| 326 | | | | | | | | For stormwater practices which require sizing: Use standard Town of Colonie rainfall amounts for the 1, 2, 10, 25, 50, 100-year 24-hour and 90% rainfall events. They are 1-yr = 2.5 ", $2-yr = 2.8$ ", $10-yr = 4.5$ ", $25-yr = 5.0$ "; $50-yr = 5.8$ "; $100-yr = 7.0$ ", and 90% rainfall (P) = 1.2 ". |
| 328 | | | | | | | | Use of City-Town-Village-County-University Standard Specifications (if any) for design of the storm drain system (i.e. catch basins, manholes, piping, etc.) |
| 329 | | | | | | | | Construction Drawings |
| 330 | | | | | | | | Stamped construction drawings and SWPPP with the signature and seal of a ' <i>Qualified Professional</i> ', as defined in GP-0-15-002 Construction Activity Permit. |
| 331 | | | | | | | | Location of existing and proposed roadways, lot boundaries, buildings, and other structures |
| 332 | | | | | | | | Location of existing and proposed utilities (e.g. water, sewer (sanitary and storm), gas, electric) and easements |
| 333 | | | | | | | | Location of existing and proposed conveyance systems (i.e. swales, MHs, CBs, pipes, etc.) |
| 334 | | | | | | | | Existing and proposed elevations for storm drain structures (i.e. pipes, CBs, manholes, etc.). Include vertical separation distances for all utilities. |
| 335 | | | | | | | | Flow paths of surface and subsurface stormwater management structures (use flow arrows) |
| 336 | | | | | | | | Locations and dimensions of all proposed channel modifications (i.e. bridges & culverts) |
| 337 | | | | | | | | Final landscaping plans - include buffer zones, reforestation, or wetland mitigation areas |
| 338 | | | | | | | | Location of sea-level rise projections along Hudson for 2020, 2050, and 2080 ClimAID Supplement Risk Information September, 2014 |